

SURVEY &  
REMONUMENTATION

APR 05 1996

COMMISSION

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Ottawa

	Located In:	Corner Code #
(County)	Wright Twp.	
1. Public Land Survey	T 8N R. 13W	J-9
	T R	1/4 corner
	T R	Section 23 & 26
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED  
95 DEC 12 AM 11:51  
*D. J. Alderman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI  
Register of Deeds Stamp & File Number

I, Carl P. Englert, Jr., in a field survey on October 31, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-9 1/4 corner common to Sections 23 & 26  
Original Corner set September, 1838  
by Enock Hammele  
Set 1/4 section post:  
Beech 8" N 62° W 25 Links  
Maple 12" S 50° W 11 Links

LCRC Liber 1, Page 199, 4/10/1971  
Fd Stones & Crockery with 1" Iron above  
24" Maple N 05° E 25.65'  
Fe Post N 10° W 32.35'  
24" Maple S 10° W 25.15'  
MBT Pole S 06° W 53.70'

see other side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-9 1/4 corner common to Sections 23 & 26  
Found 4" CIM in Mon Box  
Found P. Pole South 53.82'

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 11/20/95

*Walter D. Redwood*  
WDR

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9 1/4 corner common to Sections 23 & 26  
4" CIM in Mon Box in CL of Asphalt Road  
Ottawa County Remonumentation Tag and Nail in S. Side 14" Maple N 69° W 139.16'  
Ottawa County Remonumentation TAG and Nail in S. Side P.P. N 70° E 217.01'  
Ottawa County Remonumentation Tag and Nail in E. Side P.P. S 02° E 53.82'  
Ottawa County Remonumentation Tag and Nail in W. Side 24" Elm S 01° E 145.33'  
NW Corner of garage (Concrete Block) S 45° E 100.64'

Signed by Carl P. Englert Jr.  
Surveyor's Michigan License No. 18987

Date 11/10/1995



J-9 T8N R13W  
LCRC Liber 1, Page 771, 10/1/72  
Fd 1/2" iron  
Nail in P.P. S. 53.70'  
Spike in 18" Maple NW 44.78'

LCRC Liber 3, Page 54  
Found 1" pipe, Set Cast iron Monument  
P. Pole S. 53.82'  
22" Maple NW 45.20'

4 11.00 CORNER