

**SURVEY & REMONUMENTATION**

APR 24 1995

**COMMISSION**

For corners in

Ottawa

(County)

OTTAWA COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:53

*Elizabeth Ballman*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>13W</u>	J-11 (N $\frac{1}{4}$ , 35) Wright Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Donald W. Schiele, in a field survey on November 29, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 J-11  $\frac{1}{4}$  corner common to Sections 26 & 35, Wright Twp.  
 Original Government L.C.R.C. recorded in Liber 2,  
 Corner Record: Page 129, 5-7-73  
 Set qr sec post between Spike  
 Sec. 26 & 35. S.E. T.P. 61.36'  
 Post N.E. Fence Post 25.04'  
 Sugar 12 S12W 6 S. Iron Stake 32.62'  
 Do 14 N14W 42

L.C.R.C. recorded in Liber 3,  
 Page 17, 12-11-75  
 Found  $\frac{1}{2}$ " round iron  
 Nail in T. Pole ESE 61.63'  
 Nail in T. Pole WSW 163.71'  
 Nail in twin 12" Oak N 56.31'

(SEE REVERSE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 J-11 Found Cast Iron Monument inscribed "Section Corner", 7" below surface in Monument Box, and accepted as a careful and faithful perpetuation of the position of the original corner.  
 Found nail in NW side of Telephone Pole S60°E 61.25'  
 Found PK nail in SW side of Telephone Pole S60°E 61.53'  
 Found nail in SW side of Telephone Pole S60°E 61.54'  
 Found nail in NE side of 16" Apple S33°E 54.85'  
 Found 1" o.d. Iron Pipe, leaning North. Used top. S01°W 32.47'  
 Found PK nail in South side of Telephone Pole S79°30'W 163.93'  
 Found nail in East side of 15" Twin Oak N09°W 56.54'  
 Found nail in East side of 15" Twin Oak N09°W 56.55'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 J-11 Cast Iron Monument inscribed "Section Corner", 7" below surface in Monument Box.  
 Set Ottawa County Remon Tag & nail in SW side of Telephone Pole S60°E 61.63'  
 Set Ottawa County Remon Tag & nail in NE side of 16" Apple S33°E 54.98'  
 Set Ottawa County Remon Tag & nail in NW side of 16" Pine S63°W 110.08'  
 Set Ottawa County Remon Tag & nail in SW side of Power Pole N56°30'W 95.83'  
 Set Ottawa County Remon Tag & nail in West side of 15" Twin Oak N09°W 55.44'  
 On occupation line to North, ±  
 Fence line to South, 4' East  
 Centerline asphalt road East & West, 0.3' North

P.A. 345 OTTAWA COUNTY

PEER APPROVED 12/12/94  
*[Signature]*  
 Date Dec. 12, 1994

Signed by Donald W. Schiele Date \_\_\_\_\_  
 Surveyor's Michigan License No. 23517

PART A. continued:

L.C.R.C. recorded in Liber 3, Page 50, 3-29-76

J-11

Set cast iron Mon.		
Twin 10" Oak	NNW	56.35'
10" Apple	SSE	55.05'
Tel. pole	SE	61.75'

COPE #  
DORNER  
COPE #

1930