

SURVEY & REMONUMENTATION

FEB 27 1998

Ottawa County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 8N R 13W	J-12 (C/4, 35)
	T ___ R ___	Wright Twp.
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECORDED
97 DEC -8 AM 11:30

Ray Schiele
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Donald W. Schiele, in a field survey on July 24, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

J-12 Central 1/4 corner, Section 35, Wright Twp.
Original Government Survey by Enoch Hammele, Deputy Surveyor, for Rasselas Whitcomb, Deputy Surveyor, between 9-18 and 9-26, 1838. Corner not set.
L.C.R.C. recorded in Liber 2, Page 129, 5-7-73:
J-12 3/4" Pipe
S.E. 29.63 P.P.
N.W. 63.80 36" Oak
N.N.W. 77.16 S.W. Cor. Hse.
N.E. 33.82 T.P.

P.A. 345 OTTAWA COUNTY

PEER APPROVED 12-1-97

YDN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-12 Found Cast Iron Monument (broken) in Monument Box.
Found nail in NW side of Power Pole N59°E 33.81'(E)
Found nail in SW side of Power Pole S27°30'E 29.62'(E)
Found nail in SW side of Power Pole S27°30'E 29.26'(E)
Found nail in NW side of Power Pole S27°30'E 28.80'(E)
Found PK nail in NE side of Power Pole S27°30'E 29.57'(E)
Found nail in SW side of 40" Maple N54°30'W 63.67'(E)
SW building corner N12°W 77.13'(E)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-12 Broken Cast Iron Monument in Monument Box.
Set Ottawa County Remon Tag & nail in SE side of Power Pole N59°E 33.78'(E)
Set Ottawa County Remon Tag & nail in NE side of Power Pole S46°30'E 55.58'(E)
Set Ottawa County Remon Tag & nail in NE side of Power Pole S27°30'E 29.50'(E)
Set Ottawa County Remon Tag & nail in SW side of 40" Maple N54°30'W 63.68'(E)
SW building corner N12°W 77.13'(E)

\$ 9.00 CORNER
\$ 1.00 PHOTO

Signed by Donald W. Schiele
Surveyor's Michigan License No. 23517

Date Nov. 26, 1997