

APR 05 1996

COMMISSION

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ottawa (County)	Located In: Wright Twp.	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>13W</u>	<u>K-6</u>
	T <u>    </u> R <u>    </u>	<u>W 1/4 Corner</u>
	T <u>    </u> R <u>    </u>	<u>Section 13</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

RECORDED

95 NOV 29 PM 1:41

*Reginald R. Holloman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Carl P. Englert, Jr., in a field survey on October 31, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-6 1/4 corner common to Sections 13 & 14  
Original Corner set September, 1838  
by Enock Hammele  
Set 1/4 Section Post  
B Alder 6" West 14 Links  
Willow 12" S. 05° E 28 Links

LCRC Liber 5, Page 167, 12/14/1984  
Set CIM  
Street Sign W. 19.8'  
Tele. Ped. WNW 36.2'  
Sign Post WNW 21.15'  
Sign Post ENE 67.28'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6 1/4 corner common to Sections 13 & 14  
Found 3" Cast Iron Mon. in Mon. Box  
Found Street Sign W. 19.8'  
Found Tele. Ped. WNW 36.2'  
Found Sign Post WNW 21.15'

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 11/20/95  
*Richard P. Hedewell*  
RPH

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6 1/4 corner common to Sections 13 & 14  
3" Cast Iron Monument in Mon Box 1.5'± W. of CL Asphalt Road  
Ottawa County Remonumentation tag and nail in N. side P.P. S 57° W 238.94'  
Ottawa County Remonumentation tag and nail in N. side 24" Oak N 89° W 393.43'  
Ottawa County Remonumentation tag and nail in S. Side P.P. N 69° E 205.21'  
SE Corner Metal Pole Building N 16° W 375.28'

Signed by Carl P. Englert Jr.  
Surveyor's Michigan License No. 18987

Date 11/10/1995

