

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Ottawa
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>8N</u> R <u>13E</u>	K-7 (SE, 14)
	T _____ R _____	Wright Twp.
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED

96 DEC 17 AM 10:43

Donald W. Schiele
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Donald W. Schiele, in a field survey on November 4, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-7 Corner common to Sections 13, 14, 23 & 24, Wright Twp.
Original Government Corner Record: Ottawa County Surveyor Records:
Set post cor to secs 13,14,23 & 24 Stone
Post F. Post N33W 33
Sugar 9 N52E 23 F. Post S33W 33
Do 14 S49W 26
Found Stone & Wood Stake, Placed Iron 8-27-51
Enoch Hammele, Deputy Surveyor, for C/L 30" Elm SE 76.7
Rasselas Whitcomb, Deputy Surveyor P.P. NW 43.4
Between 9-18 and 9-26, 1838 C/L 14" Maple NW 94.3 (SEE REVERSE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-7 Found 1" o.d. x 24" Iron Pipe, 2" below asphalt surface in Monument Box, and accepted as a careful and faithful perpetuation of the position of the original corner.
West corner, Concrete Project Marker N45°00'E 34.41'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11-11-96

D.W.S.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-7 Removed 1" o.d. x 24" Iron Pipe and replaced with 3/4" x 24" Steel Bar with Ottawa County Remon Cap, 2" below asphalt surface in Monument Box.

Southwest corner, foundation to house	N32°30'E	137.33'(E)	\$ 1.00 PHOTO	\$ 11.00 CORNER
West corner, Concrete Project Marker	N45°00'E	34.41'(E)	\$ 1.00 PHOTO	\$ 11.00 CORNER
Set Ottawa County Remon Tag & nail in South side of Power Pole	N84°30'E	153.15'(E)	\$ 1.00 PHOTO	\$ 11.00 CORNER
Set Ottawa County Remon Tag & nail in SW side of Power Pole	S32°30'E	306.93'(E)	\$ 1.00 PHOTO	\$ 11.00 CORNER
Set Ottawa County Remon Tag & nail in North side, Northerly pole, power line support	S85°30'W	343.82'(E)	\$ 1.00 PHOTO	\$ 11.00 CORNER
Centerline asphalt road North & South, 0.4' West				
On centerline gravel road East				
Centerline gravel road West, 2.0' North				

Signed by Donald W. Schiele Date November 11, 1996
Surveyor's Michigan License No. 23517

Part A., continued:

K-7

Fd 1" Iron Pipe, C.P.Co.		
12" Maple	NW	34.63
Power Pole	NW	45.00
West Corner Project Marker	NE	34.39
Electric Pole	SE	88.30