

**SURVEY & REMONUMENTATION**

APR 05 1996

**COMMISSION**

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Ottawa \_\_\_\_\_  
(County)

Located in: Wright Twp.

Corner Code #

1. Public Land Survey	T8N R 13W	K-8
	T _____ R _____	W 1/4 Corner
	T _____ R _____	Section 24
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

**RECORDED**  
95 NOV 29 PM 1:46  
*D. J. ...*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Carl P. Englert, Jr., in a field survey on October 31, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of Survey Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-8 1/4 corner common to Sections 23 & 24  
Original Corner Set September, 1838  
by Enock Hammele  
Set 1/4 Section Post  
Beech 9" S 23° E 9 Links  
Beech 9" N 67° W 39 Links

LCRC Liber 2, Page 429, 12/31/1973  
Fd 3/8" Iron and Stone, Set Ottawa County Monument  
N in Side 8" Apple SW 59.17'  
N in Side Fe Post W 28.18'  
SW Cor Brick House ENE 189.86'  
NW Cor Garage SE 180.12'  
CL Bldg Pvt. E 3.1' on fence lin West

see other side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 1/4 corner common to Sections 23 & 24  
Found 4" CIM in Mon Box  
Found SW Cor. Brick House ENE 189.86'  
Found NW Cor. Garage SE 180.12'  
Found 12" Triple Maple NNE 85.38'


RA. 345 OTTAWA COUNTY  
PEER APPROVED 11-20-95  
*Medoy D. Medowald*  
YDN

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 1/4 corner common to Sections 23 & 24  
4" Cast Iron Mon with Broken Top in Mon Box 3'± W. of CL Asphalt Road  
NW Corner (brick) Garage S 45° E 180.21'  
NW Corner Metal Bldg. S 73° E 157.27'  
Ottawa County Remonumentation Tag and Nail in SE side 12" Ash N 54° E 64.00'  
Ottawa County Remonumentation Tag and Nail in W. side 12" Triple Maple N 26° E 85.16'  
Ottawa County Remonumentation Tag and Nail in N. side P.P. N 86° W 34.33'

Signed by Carl P. Englert Jr.  
Surveyor's Michigan License No. 12927



11/10/1995

APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1971  
REVISED JAN., 1971  
REVISED OCT., 1971

K-8 T8N, R13W  
LCRC Liber 2, Page 663, 10/1/1974  
Found steel Mon. Marked Ottawa County Section Corner  
PK Nail in fence post W 28.07'  
Nail in 5" Maple NNE 85.38'  
Spike in 8" Apple Tree S.W. 59.35'

\$ 11.00 CORNER