

SURVEY & REMONUMENTATION

APR 05 1996

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Ottawa

(County)

Located in:

Wright Twp.

Corner Code #

1. Public Land Survey

T 8N R 13W K-9
T R NE Corner
T R Section 26
T R

2. Property Controlling in Section

S T R
S T R

3. Miscellaneous Property in Sec.

S T R
S T R

RECORDED

95 DEC 12 AM 11:51

Richard L. ...
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, Carl P. Englert, Jr., in a field survey on November 2, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-9 Corner common to Sections 23, 24, 25, and 26
Original Corner set September, 1838
by Enock Hammele
Set post cor. to Sections 23, 24, 25 and 26
Hickory 10" S. 37° W 13 Links
Sugar 12" N. 39° E 32 Links

LCRC Liber 1, Page 771, 10/1/1972
R.R. Spike in Mon Box
SW Cor Hse Fnda. SE 124.47'
Nail in T.P. N.E. 45.97'

see other side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9 Corner common to Sections 23, 24, 25, and 26
Found R.R. Spike in Mon. Box with a Boat Spike bent around a stone beneath the R.R. Spike.
Set 3/4" Steel bar with Ottawa County Remonumentation cap over boat spike and stone.
Found 28" Maple SSW 70.19'
Found P. Pole SE 66.54'
Found 26" Maple WSW 67.28'

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9 Corner common to Sections 23, 24, 25 and 26
3/4" steel bar with Ottawa County Remonumentation Cap over Stone & Boatspike in Mon Box
Ottawa County Remonumentation tag and nail in N side 26" Maple S 63° W 67.31'
Ottawa County Remonumentation tag and nail in E side 26" Maple S 27° W 70.19'
Ottawa County Remonumentation tag and nail in W side P.P. S 37° E 66.12'
Ottawa County Remonumentation tag and nail in E side 8" Pine N 26° W 121.48'
in CL of intersection.

PA. 345 OTTAWA COUNTY

PEER APPROVED 11/20/95

Signed by

Carl P. Englert Jr.

Surveyor's Michigan License No.

18987

Richard D. ...
Date 11/20/95



K-9 T8N R13W
LCRC Liber 4, Page 93, July 30, 1980
Found R.R. Spike in Mon Box
28" Maple SSW 70.19'
P.P. SE 66.54'
36" Maple WSW 67.28'

11:00
CORNER