

SURVEY &
REMONUMENTATION

APR 05 1996

OTTAWA COUNTY REMONUMENTATION
COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ottawa	Located In:	Corner Code #
(County)	Wright Twp.	
1. Public Land Survey	T 8N R 13W	K-10
	T R	W 1/4 Corner
	T R	Section 25
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECORDED

95 NOV 29 PM 1:46

Richard K. Kellerman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl P. Englert, Jr., in a field survey on October 31, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-10 1/4 corner common to Sections 26 & 25	LCRC Liber 2, Page 761, 3/28/1975
Original corner set September, 1838	Found R.R. Spike
by Enoch Hammele	CL Road N-S
Set 1/4 section post	8" C. Elm E 70.25'
Maple 16" N 48° E 3 Links	12" Apple N 30° E 90.90'
Beech 9" S 71° W 22 Links	C.P. Pole S 40° E 88.77'
	CL W. end 36" Culvert S 40° W 47.70'

see other side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-10 1/4 corner common to Sections 26 & 25
 Found 4" Cast Iron Monument in Monument Box in CL Asphalt Pavement
 Found CL West end 36" Culvert SW 47.70'
 Found P.Pole S 40° E 88.77'

PA. 345 OTTAWA COUNTY
 PEER APPROVED 11-20-95

Richard P. Redwood

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10 1/4 corner common to Sections 26 & 25
 4" Cast iron monument in Monument box in CL asphalt pavement
 Cut Cross in W. end concrete culvert S 42° W 47.45'
 Ottawa County Remonumentation tag and nail in SE Side 50" Willow N 13° E 174.24'
 Ottawa County Remonumentation tag and nail in E. side P.P. N 12° W 244.78'
 Ottawa County Remonumentation tag and nail in NE side P.P. S 33° E 88.47'
 Ottawa County Remonumentation tag and nail in NW side 8" Pine N 44° E 47.44'

Signed by Carl P. Englert Jr.
 Surveyor's Michigan License No. 18987

Date 11/8/1995



K-10 T8N, R13W
LCRC Liber 3, Page 50
Found Railroad Spike, Set Cast Iron Monument
8" Elm E 70.25'
12" Apple NE 90.90'
P. Pole SE 88.77'
CL West End 36" Culvert SW 47.7'

\$ 11.00 CORNER