

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:46

Register of Deeds
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>13W</u>	<u>K-12 (W 1/4, 36)</u> <u>Wright Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald W. Schiele, in a field survey on November 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-12 - 1/4 corner common to Sections 35 & 36, Wright Twp.
Original Government Corner Record: L.C.R.C. recorded in Liber 3, Page 95, 6-18-76
Set qr sec post between Sec. 35 & 36 Iron in MB
Post SE cor hse NW 90.98'
Beech 16 S40W 18 PK in sde P. Pole SW 60.92'
Do 10 S19E 20 PK in sde cor fe post East 27.37'
Enoch Hammele, Deputy Surveyor
Between 9-18 and 9-26, 1838

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-12 Found 2-3/4" dia. Cast Iron Monument (broken), 7" below surface in Monument Box, and accepted as a careful and faithful perpetuation of the position of the original corner.
Found PK nail in North side of single Fence Post S87°E 28.27'
Found nail in NE side of Power Pole S50°30'W 60.53'
Found PK nail in SE side of Power Pole S50°30'W 60.99'
Found nail & MSHD Tag in NW side of Power Pole S50°30'W 61.19'
SE frame corner to House # 14815 N56°W 90.93'
Found nail in SE side of Power Pole N50°30'W 58.19'
Found PK nail in NE side of Power Pole N50°30'W 58.66'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 Broken 2-3/4" dia. Cast Iron Monument, 7" below surface in Monument Box.
Set Ottawa County Remon Tag & nail in North side of 16" Twin Maple East 175.43'
Set Ottawa County Remon Tag & nail in NW side of Power Pole S50°30'W 61.07'
SE frame corner to House # 14815 N56°W 90.93'
Set Ottawa County Remon Tag & nail in East side of 17" Maple N26°W 89.80'
Centerline asphalt road North & South, 0.3' West
Centerline asphalt road West, 1' South
Fence line to East, 2' South

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

Signed by Donald W. Schiele

Date Dec 12, 1994

Surveyor's Michigan License No. 23517