

**SURVEY &  
REMONUMENTATION**

APR 05 1996

**OPTAWA COUNTY REMONUMENTATION  
COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>OTTAWA</u> (County)	Located In: Wright Twp.	Corner Code # L-3
1. Public Land Survey	T 8N R 13W	S 1/4 corner Section 1
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

**RECORDED**  
95 DEC 12 AM 11:50  
*Elizabeth Holliman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI  
**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Carl P. Englert, Jr., in a field survey on 11/17, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
L-3 1/4 corner common to Sections 1 & 12  
Original Gov't corner set September 1838 by Enoch Hammele  
Set 1/4 section post  
Sugar 9" N 84° E 7 links  
Beech 12" S 21° W 8 links  
LCRC Liber 3, Page 68, 1/14/1976  
Found boat spike, glass, pottery & stone with cross  
Set cast iron monument  
P. Pole WNW 158.03'  
P. Pole ENE 120.84'  
10" Apple NNW 68.33'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
L-3 1/4 corner common to Sections 1 & 12  
Found 4" cast iron monument in monument box on centerline asphalt road  
Found P.P. WNW 158.03'  
Found P.P. ENE 120.84'

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
L-3 1/4 corner common to sections 1 and 12  
4" cast iron monument in monument box on centerline asphalt road  
Ottawa County Remonumentation tag and nail in S side P.P. N 69° W 158.59'  
Ottawa County Remonumentation tag and nail in SE side P.P. N 62° E 120.82'  
Ottawa County Remonumentation tag and nail in top of R.R. tie used as anchor post  
N 24° W 53.76'  
Centerline 3" Apple S 08° W 60.86'  
P.A. 345 OTTAWA COUNTY

PEER APPROVED 11/20/95

Signed by Carl P. Englert Jr.  
Surveyor's Michigan License No. 18987

*Walter D. Hedgewell*  
Date 11/20/1995

