

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE 94 DEC 14 AM 9:41
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 8N R 13W	L-5 (N $\frac{1}{4}$, 13) Wright Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Edythe S. Williams
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Donald W. Schiele, in a field survey on December 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented; recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-5 $\frac{1}{4}$ corner common to Sections 12 & 13, Wright Twp.
 Original Government L.C.R.C. recorded in Liber 3, L.C.R.C. recorded in Liber 6,
 Corner Record: Page 60, 3-29-76 Page 96, 1-28-91
 Set qr sec post Set cast iron Mon. Set CIM
 between Sec. 12 & 13 P. pole S 24.48' TP N 25.82'
 Post Tel. pole N 25.71' PP S 28.29'
 Beech 14 N 9W 20 10" Apple SW 70.82'
 Do 9 S76E 24
 Enoch Hammele, Deputy surveyor
 Between 9-18 and 9-26, 1838

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-5 Found 2-3/4" dia. Cast Iron Monument inscribed "Section Corner", 1/2" below surface in Monument Box, and accepted as a careful and faithful perpetuation of the position of the original corner.
 Found PK nail in East side of Power Pole S03°E 28.29'
 Centerline 16" Apple S57°W 70.8'
 Found PK nail in East side of Telephone Pole N03°30'W 25.78'

PA. 345 OTTAWA COUNTY
 PEER APPROVED 12/12/94

Robert P. Newell

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 L-5 2-3/4" dia. Cast Iron Monument inscribed "Section Corner", 1/2" below surface in Monument Box.

Set Ottawa County Remon Tag & nail in North side of Power Pole S85°30'E 351.34'(E)
 Set Ottawa County Remon Tag & nail in East side of Power Pole S03°E 28.40'
 NW corner, brick planter to House # 420 S40°W 102.93'
 Set Ottawa County Remon Tag & nail in West side of 11" Elm N02°30'W 50.91'
 Centerline drain to North, 7' West
 On occupation line to South, ±
 Centerline asphalt road East & West, 0.3' South

Signed by Donald W. Schiele Surveyor's Michigan License No. 23517

Date DEC. 12, 1994

