

**SURVEY & REMONUMENTATION**

APR 24 1995

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 15 AM 11:47

**COMMISSION**

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>13W</u>	<u>L-11 (N<math>\frac{1}{4}</math>, 36)</u> <u>Wright Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Phyllis Chelmsford*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Donald W. Schiele, in a field survey on November 30, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

L-11 $\frac{1}{4}$ corner common to Sections 25 & 36, Wright Twp.	L.C.R.C. recorded in Liber 2, Page 761, 4-3-75	L.C.R.C. recorded in Liber 3, Page 52, 3-29-76
Original Government Corner Record:	Iron	Set cast iron Mon.
Set qr sec post between Sec. 25 & 36	28" Maple NE 30.2'	30" Maple NE 31.33'
Post	36" Maple ENE 160.0'	16" Cherry SE 54.85'
Beech 10 S71E 9	Fe post N 32.0'	
Do 15 N22W 25	Fe post S 21.0'	
Enoch Hammele, Deputy Surveyor	NW cor hse fnd SE 82.8'	
Between 9-18 and 9-26, 1838	NE cor hse fnd SE 92.9'	

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

L-11 Found Cast Iron Monument inscribed "Ottawa County Section Corner", 5" below surface, and accepted as a careful and faithful perpetuation of the position of the original corner.

Centerline 36" Stump	N27°E	31.5'
Centerline 40" Triple Maple	N79°30'E	161.7'
NE corner, foundation to House # 364	S37°30'E	92.92'
NW corner, foundation to House # 364	S24°E	82.87'
Centerline Fence Post	N01°W	32.4'

P.A. 345 OTTAWA COUNTY


PEER APPROVED 12/12/94

*Gayle P. Nedewold*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-11 Cast Iron Monument inscribed "Ottawa County Section Corner", 5" below surface.

Set Ottawa County Remon Tag & nail in NE side of 18" Spruce	S57°30'E	84.23'
NW corner, foundation to House # 364	S24°E	82.87'
Set Ottawa County Remon Tag & nail in SW side of 11" Spruce	N48°W	55.23'
Set Ottawa County Remon Tag & nail in West side of 24" Maple (Westernmost of cluster)	N02°W	70.40'
Centerline Fence Lines to North & South, 1'± East		
On centerline gravel road East & West		



Signed by Donald W. Schiele

Date DEC. 12, 1994

Surveyor's Michigan License No. 23517