

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:41

For corners in

Ottawa
(County)

Located In:

Corner Code #/

- | | | | | | |
|------------------------------------|---|-----------|---|------------|---------------------|
| 1. Public Land Survey | T | <u>8N</u> | R | <u>13W</u> | <u>M-5 (NE, 13)</u> |
| | T | _____ | R | _____ | <u>Wright Twp.</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Phyllis Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Donald W. Schiele, in a field survey on December 9, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-5 SE corner, Section 12 & NE corner, Section 13, Wright Twp.

Original Government Corner Record: L.C.R.C. recorded in Liber 5, Page 329, 8-9-88

Set corner post Sec. 12 & 13

Set CIM

Post

PP

NE 69.96'

Sugar 10 S55W 22

PP

SE 53.05'

Beech 9 N22W 36

C/L Street Sign

S 24.63'

Noah Brookfield, Deputy Surveyor

PP

SW 91.85'

April 26, 1837

PA. 345 OTTAWA COUNTY

PEER APPROVED 12/12/94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5 Found Cast Iron Monument inscribed "Section Corner", 4 1/2" below surface in Monument Box, and accepted as a careful and faithful perpetuation of the position of the original corner.

Found nail & Tag # 18435 in NW side of Power Pole	N48°E	69.94'
Found PK nail in NW side of Power Pole	N48°E	69.94'
Found nail in NW side of Power Pole	N48°E	69.95'
Found nail & Tag # 18435 in NE side of Power Pole	S60°E	53.07'
Found PK nail in NE side of Power Pole	S60°E	53.05'
Found nail in SW side of Power Pole	S60°E	53.08'
Found nail & Tag # 18435 in SE side of Telephone Pole	S64°30'W	91.83'
Found Kent County Remon Tag & nail in NW side of Power Pole	S72°W	86.68'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5 Cast Iron Monument inscribed "Section Corner", 4 1/2" below surface in Monument Box.

Set Ottawa County Remon Tag & nail in SE side of Power Pole	N48°E	69.89'
Set Ottawa County Remon Tag & nail in NE side of Power Pole	S60°E	53.18'
Chiselled "X" in East end of 12" Concrete Culvert	S20°W	21.23'
Set Ottawa County Remon Tag & nail in NW side of Power Pole	S72°W	86.64'
Centerline gravel road North, 4' East		
On occupation line to South, ±		
Centerline asphalt road East & West, 1' South		



Signed by Donald W. Schiele

Date Dec. 12, 1994

Surveyor's Michigan License No. 23517