

FEB 24 2000

RECORDED

99 DEC -2 PM 1:14

SECTION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Sam Schiele
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>13W</u>	M-8(E $\frac{1}{4}$, 24) <u>Wright Twp.</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Donald W. Schiele, in a field survey on 11/12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
M-8 East 1/4 corner, Section 24, Wright Twp.

Original Government Corner Record:	L.C.R.C. recorded in L.2, P.429, 2-20-74 by
Set qr sec Post	Douglas W. Bonnema:
Post	M-8 Monument.
Beech 18 S22W. 21	Nail in side Walnut ESE 57.89'
do 18 N37W. 20	Nail in side 30" Oak NNW 141.83'
Noah Brookfield, Deputy Surveyor	Nail in side P. Pole WNW 155.45'
April 26, 1837	Underground phone term. box W 21.0'
	C/L "X" Gravel rd (to S & E) E 11'±

(SEE REVERSE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

M-8 Found Cast Iron Monument inscribed "Ottawa County Section Corner", 4" below ground level at West edge of gravel road, and accepted as a careful and faithful perpetuation of the position of the original corner.

Found Kent County Remon Tag & nail in NW side of Power Pole	N59°E	48.35' (E)
Face of 14" dead tree	S76°30'E	95.8' (E)
Face of 15" dead tree	S67°30'E	57.4' (E)
Found nail in North side of 15" dead tree	S67°30'E	57.83' (E)
Found cut "X" in South end of 12" Concrete Culvert	S11°30'W	38.32' (E)
Found Kent County Remon Tag & nail in SE side of 14" Boxelder	S70°30'W	23.03' (E)
C/L Underground Phone Terminal Box	N89°30'W	20.93' (E)
C/L 40" Oak	N26°30'W	142.0' (E)


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 Cast Iron Monument inscribed "Ottawa County Section Corner", 4" below ground level at West edge of gravel road.

Set Ottawa County Remon Tag & nail in NW side of Power Pole	N59°E	48.40' (E)
Cut "X" in South end of 12" Concrete Culvert	S11°30'W	38.32' (E)
Set Ottawa County Remon Tag & nail in SE side of 14" Boxelder	S70°30'W	23.02' (E)
Set Ottawa County Remon Tag & nail in South side of 10" Pine	N69°30'W	105.74' (E)

On occupation line to North (extended South), ±.
On centerline of gravel road to East.
Centerline gravel road to South, 11' East.
Centerline ditch to West, 6' South.

Signed by Donald W. Schiele Donald W. Schiele Date November 12, 1999
Surveyor's Michigan License No. 23517



\$11.00 CORNER
Receipt #64945

FEB 24 2000

SECTION

Part A., continued;

L.C.R.C. #8423, recorded 6-29-95 in Kent County, MI by Kirk Breitels:

A-8 (T8N, R12W): Standard Ottawa County Monument

South face of Twin 20" Box Elder	N48°W	94.4'
South face of 36" Oak	N30°E	140.6'
Northwesterly face of 14" Walnut-dead	S70°E	57.3'
Northwesterly face of 14" Walnut-dead	S80°E	95.7'
Cut "X" top of conc. culv.	S10°W	38.27'
Set Nail & KC Remon. tag S. side 12" Box Elder	S70°W	23.08'
Set Nail & KC Remon. tag NW side Power Pole	N60°E	48.41'
On C/L Rd. to East and tree line West		
C/L rd. to North-South is East 11' m/l		