

**SURVEY &
REMONUMENTATION**

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

APR 24 1995

94 DEC 15 AM 11:47

For corners in
Ottawa **COMMISSION**
(County)

Located In: Corner Code #

- | | | |
|---------------------------------------|--------------------------|------------------------------|
| 1. Public Land Survey | T <u>8N</u> R <u>13W</u> | M-11 (NE, 36)
Wright Twp. |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Richard L. ...
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald W. Schiele, in a field survey on November 29, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-11 SE corner, Section 25 & NE corner, Section 36, Wright Twp.
Original Government Corner Record: L.C.R.C. recorded in Liber 3, Page 52, 3-29-76
Set corner post of Sec. 25 & 36 Set cast iron Mon.
Post P. pole SE 116.40'
Beech 10 S 9W 14 C/L St. sign NE 40.92'
Do 10 N46W 32 C/L St. sign WSW 38.70'
Noah Brookfield, Deputy Surveyor 3" Cherry NNE 68.10'
April 26, 1837.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 Found Cast Iron Monument inscribed "Ottawa County Section Corner", 4" below surface, and accepted as a careful and faithful perpetuation of the position of the original corner.
Found nail in NW side 6" Cherry N24°E 68.07'
Found nail in NE side of Power Pole S67°E 116.34'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Melody D. Nedewell



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 Cast Iron Monument inscribed "Ottawa County Section Corner", 4" below surface.
Set Ottawa County Remon Tag & nail in NW side of 6" Cherry N24°E 68.06'
Set Ottawa County Remon Tag & nail in NE side of Power Pole S67°E 116.19'
Set Ottawa County Remon Tag & nail in NE side of 11" Willow S53°E 80.70'
Set Ottawa County Remon Tag & nail in East side of corner Fence Post S14°30'E 30.77'
Set Ottawa County Remon Tag & nail in SE side of Power Pole S69°W 126.97'
On centerline, gravel roads to North & West
On centerline, asphalt road to East
Centerline fence line to South, 35' East

Signed by Donald W. Schiele Date Dec. 12, 1994

Surveyor's Michigan License No. 23517