

**SURVEY &
REMONUMENTATION**

APR 05 1996

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
OTTAWA

	Located In:	Corner Code #
(County)	Polkton Twp.	
1. Public Land Survey	T 8N R 14W	A-2
	T R	W 1/4 Corner
	T R	Section 6
	T R	
2. Property Controlling in Section	S T R	Common corner
	S T R	w/ M-2
3. Miscellaneous Property in Sec.	S T R	Crockery Twp.
	S T R	

RECORDED
95 NOV 29 PM 1:47
Edythe A. Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl P. Englert, Jr., in a field survey on November 16 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-2 1/4 corner common to Section 6, T8N, R14W and Section 1, T8N, R15W
LCRC Liber 2, Page 253, 8/3/1973
Original Gov't Corner set March 1837 Found 5/8" Rod
by John Mullett ESE 89.3' NW corner House
Set 1/4 Section Post W. 26.36' T.P.
B. Oak 36" S 30° W 45 Links NE 51.70' T.P.
Beech 7" N 43° W 12 Links

see other side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-2 1/4 corner common to Section 6, T8N, R14W and Section 1, T8N, R15W
Found 4" Cast Iron Monument with top broken off 3" below grade in CL of Gravel
Road on Occupation Line E & W.
Found ESE NW corner of House 89.3'
Found P.P. NE 51.70'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11-20-95

Edythe A. Robinson
YON

Accepted as a careful and faithful perpetuation of the original position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2 1/4 corner common to Section 6, T8N, R14W and Section 1, T8N, R15W
4" Cast Iron Monument 3" below grade in CL Gravel Road.
Ottawa County Remonumentation tag and nail in E. side P.P. N 24° W 157.38'
Ottawa County Remonumentation tag and nail in SE side P.P. N 39° E 51.56'
Ottawa County Remonumentation tag and nail in SW side 12" Maple S 52° E 51.46'
Ottawa County Remonumentation tag and nail in S. side Tele pole West 25.82'

Signed by Carl P. Englert Jr
Surveyor's Michigan License No. 18987

Date 11/20/1995



A-2 T8N, R14W
LCRC Liber 2, Page 423 11/29/73
Fd. 5/8" rod
ESE 89.3' NW Cor Hse
W. 26.36' T.P.
NE 51.70' T.P.

LCRC Liber 4, Page 97 8/12/80
Found 5/8" Iron Bar, Set Cast Iron Monument
T.P. W. 26.27'
T.P. NE 51.70'
NW Corner of House East 96.72'

\$ 11.00 CORNER