

FEB 24 2000

RECORDED

SECTION

OTTAWA COUNTY REMONUMENTATION

99 DEC -2 PM 1:13

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Dan S. Vugteveen*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in  
OTTAWA  
(County)

Located In:	Corner Code #
T <u>8N</u> R <u>14W</u>	A-5 NW corner
T <u>    </u> R <u>    </u>	Section <u>18</u> , Polkton
T <u>    </u> R <u>    </u>	Twp <u>    </u>
T <u>    </u> R <u>    </u>	
S <u>    </u> T <u>    </u> R <u>    </u>	
S <u>    </u> T <u>    </u> R <u>    </u>	
S <u>    </u> T <u>    </u> R <u>    </u>	
S <u>    </u> T <u>    </u> R <u>    </u>	

Register of Deeds Stamp & File Number

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Randal J. Vugteveen, in a field survey on September 16, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-5 GLO March 1837 (John Mullett)  
Set Post for M-5 Corner Crockery Twp  
9" Birch S23°W 32 Links  
20" Sugar Maple N14°W 22 Links  
GLO notes held post for A-5

A-5 Liber 4, Page 271  
Joiner December 3, 1981  
(As M-5 T8N, R15W)  
10" Ash W 39.40'  
14" Maple NE 82.70'  
Telephone Pole W 24.36'  
Twin Ash SE 87.35'

M-5 T8N, R15W Liber 4, Page 350  
3/4" X 24" Iron Bar with O.C. Remon Cap  
Nail & Remon Tag NW side 5" Maple N45°E 77.31'  
Nail & Remon Tag NE side Twin 12" Apple N64°W 46.35'  
Nail & Remon Tag E side T. pole N12°W 169.86'  
Nail & Remon Tag S side corner fence post N90°E 34.79'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

A-5 Found Iron Bar with Ottawa County Remon Cap

Nail & Remon Tag NW side 5" Maple N45°E 77.31'  
Nail & Remon Tag NE side Twin 12" Apple N64°W 46.35'  
Nail & Remon Tag E side T. Pole N12°W 169.86'  
Nail & Remon Tag S side corner fence post N90°E 34.79'  
On centerline gravel road (to be paved Oct '99)  
On center of old fence lines to E & W

Accepted iron bar with Ottawa County Remon Cap as a careful and faithful perpetuation of the position of the original corner.

11/15/99  
*[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

A-5 Iron Bar with Ottawa County Remon Cap

Nail and Remon Tag in NW side 5" Maple N45°E 77.31'  
Nail and Remon Tag in NE side Twin 12" Apple N64°W 46.35'  
Nail and Remon Tag in E side telephone pole N12°W 169.86'  
Nail and Remon Tag in S side corner fence post N90°E 34.79'  
On centerline gravel road (to be paved October 1999)  
On center of old fence lines to East and West  
Corner is common to M-5, T8N, R15W



\$11.00 CORNER  
Receipt #64945

Signed by *Randal J. Vugteveen*  
Surveyor's Michigan License No. 28429

Date OCTOBER 27, 1999

FEB 24 2000

SECTION

990003  
Mile 2  
9/16/99

