

SURVEY & REMONUMENTATION

APR 05 1996

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

For corners in

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

Ottawa (County)	Located In:	Corner Code #
	Polkton Twp.	A - 6
1. Public Land Survey	T 8 N R 14 W	W 1/4 Corner
	T _____ R _____	Section 18
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	Common corner
	S _____ T _____ R _____	w/ M-6,
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	Crockery Twp.
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

95 NOV 15 PM 2:06

Richard A. Williams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Carl P. Englert, Jr., in a field survey on October 9, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A - 6 1/4 corner common to Section 18, T 8 N, R 14 W & Section 13, T 8 N, R 15 W.
 Original corner set March 1837 LCRC Liber 4, Page 98
 by John Mullett D.S. August 12, 1980
 Set 1/4 Section Post Fd. Iron Pipe, Set CIM
 Ironwood 8" S 50° W 48 Links P.P. West 90.42'
 Lynn 12" N 21° W 24 Links P.P. SW 305.34'
 "X" in E. End Conc Culvert
 NE 262.68'

see other side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A - 6 1/4 corner common to Section 18, T 8 N, R 14 W & Section 13, T 8 N, R 15 W.
 Found 4" CIM in Mon Box CL of Asphalt Road
 Found P.P. West 90.43'
 Found P.P. SW 305.34'

P.A. 345 OTTAWA COUNTY

PEER APPROVED 10/23/95

Richard P. Hedewell

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 6 1/4 corner common to Section 18, T 8 N, R 14 W & Section 13, T 8 N, R 15 W.
 4" CIM in Mon Box
 Ottawa County Remonumentation Tag and Nail in N. side P.P. S 87° W 90.40'
 Ottawa County Remonumentation Tag and Nail in NW side P.P. S 17° W 305.29'
 Ottawa County Remonumentation Tag and Nail in E. side P.P. N 17° W 312.16'
 Ottawa County Remonumentation Tag and Nail in E side 11" Maple N 18° E 445.40'

Signed by Carl P. Englert Jr.
 Surveyor's Michigan License No. 18987

Date 10/17/95



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

A - 6 Polkton Twp T 8 N, R 14 W
M - 6 Crockery Twp T 8 N, R 15 W
LCRC Liber 5, Page 326
Fd CIM, Raised with new CIM
P.P. W 90.43'
6" App E 38.14'
P.P. SW 45.45'
P.P. SW 305.34'
15" Maple SE 98.25'
"X" E. End Conc. Culvert 262.68'

\$ 11.00 CORNER