

OTTAWA COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 DEC 16 PM 1:01

For corners in

<u>Ottawa</u> (County)	Located In: Polkton Township	Corner Code=# A-8
1. Public Land Survey	T <u>8N</u> R <u>14W</u>	<u>W 1/4</u> Corner
	T _____ R _____	Section <u>19</u>
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

*Richard R. Robinson*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

SURVEY &  
 REMONUMENTATION

DEC 05 2000

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Carl P. Englert Jr.

I, \_\_\_\_\_, in a field survey on July 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-8  
 L.C.R.C. Liber 6, Page 245, 1/25/93  
 Pd. C.I.M. in C/L Gravel Rd. with Broken Top  
 N 11 degrees E 161.57' N&S in W side 18" Maple  
 S 16 degrees E 98.66' N&S in W side 8" Maple  
 S 16 degrees W 145.33' N&S in E side 16" Maple  
 S 79 degrees W 94.25 N&T in N side T.P.

Liber 4, Page 104, 10/14/80  
 Fd. 5/8" Bar from old ties,  
 Set C.I.M.  
 Con. Tele. Pedestal WSW 93.54'  
 underground Tel. Sign WNW  
 63.58'  
 Cen. St. Sign E. 22.81'  
 Tw. 7" Oak SW 58.97'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-8  
 Found 4" Harrison Mon. with the Broken Top and accepted as a careful & faithful perpetuation of the position of the original corner.

N 11 degrees E 161.57' 18" Maple  
 N 11 degrees E 161.57' 18" Maple  
 (18" Elm)  
 S 79 degrees W 94.25 T.P.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8 Replaced broken Harrison Mon. with 3' long 3/4" Iron Bar and O.C. Remon. Cap  
 O.C. Remon. Tag & Nail in NW side s 35 degrees W 138.07'  
 O.C. Remon. Tag & Nail in N side T.P. S 76 degrees W 94.48'  
 O.C. Remon. Tag & Nail in SW side 18" Elm N 8 degrees E 161.56'  
 O.C. Remon. Tag & Nail in E side 20" Hickory N 9 degrees W 195.10'  
 O.C. Remon. Tag & Nail in N side 5" Elm S 85 degrees E 43.24'  
 (E.D.M.)

Signed by Carl P. Englert Jr. Date December 3, 1993  
 Surveyor's Michigan License No. 18987

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS  
 STATE OF MICHIGAN  
 CARL P. ENGLERT JR.  
 LAND SURVEYOR  
 No. 18987  
 REGISTERED SURVEYOR  
 REVISED JANU. 1975  
 REVISED 300-11983