

1898
 O.C. REMONUMENTATION

OTTAWA COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
 93 DEC 16 PM 1:01

For corners in

Ottawa (County) Located In: Polkton Township Corner Code #
 1. Public Land Survey T 8N R 14W A-11
 T _____ R _____ SW Corner
 T _____ R _____ Section 30
 T _____ R _____ _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Phyllis Hallman
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Carl P Englert Jr.

I, _____, in a field survey on August 6, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-11	L.C.R.C. Liber 4, Page 106, 10/14/80
L.C.R.C. Liber 3, Page 339, 2/20/79	Fd. 1" Iron pipe from old ties
Fd. 3/8" Rod	Set C.I.M.
NE 50.14' 36" Maple	40" Maple NE 50.17'
SE 48.72' T.P.	T.P. SE 48.66'
SW 47.91' Oak	30" Oak SW 47.87'
W 41.10 24" Maple	40" Oak WNW 29.86'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


A-11
 Found 4" Harrison Cast Iron Monument 8" Deep and accepted as a careful and faithful perpetuation of the position of the original corner.
 T.P. SE 48.66'
 36" Oak SW 47.89'
 40" Maple NE 50.19'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11 4" Harrison Cast Iron Monument
 O.C. Remon. & Nail in SW side 36" Oak S 45 degrees W 47.88'
 O.C. Remon. & Nail in S side 30" Maple W 41.50'
 O.C. Remon. & Nail in NE side 17" Maple N 40 degrees W 44.50'
 O.C. Remon. & Nail in NW side 40" Maple N 45 degrees E 50.50'
 O.C. Remon. & Nail in NE side T.P. S 40 degrees E 48.72'
 Tape

Signed by Carl P. Englert Jr.
 Surveyor's Michigan License No. 18987

Date December 3, 1993



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, REVISED MAY 14, 1975, REVISED JAN., 1983