

**SURVEY & REMONUMENTATION**

OCT 07 1996

COMMISSION

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>14W</u>	<u>B-3 (N. 1/4, 7)</u> <u>Polkton Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

96 AUG 26 PM 2:03

*Richard C. Coleman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Donald W. Schiele, in a field survey on August 20, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3	•											
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

B-3 1/4 corner common to Sections 6 & 7, Polkton Twp.  
Original Government Corner Record: L.C.R.C. recorded in Liber 2, Page 423, 11-30-73  
Set qr section post between B-3 Set 5/8" Rod on Fence line South and centerline of Road  
Post S.E. 71.15' 8" Ash  
Beech 8 S16W 13 S.W. 73.80' 14" Pear Tree  
Sugar 9 N53E 14 N.W. 59.22' T.P.  
John Mullett, Deputy Surveyor  
April 16, 1837

(SEE REVERSE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-3 Found Cast Iron Monument inscribed "Section Corner", 1 1/2" below surface of gravel road, and accepted as a careful and faithful perpetuation of the position of the original corner.  
Found PK nail in West side of Power Pole N13°30'E 189.90'  
Centerline Street Sign S14°30'E 22.42'  
Found nail in SE side of 20" Pear Tree S57°30'W 73.72'  
Found nail in West side of Wood Post N22°30'W 59.21'

P.A. 345 OTTAWA COUNTY

PEER APPROVED 8-20-96

*Donald W. Schiele*



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-3 Cast Iron Monument inscribed "Section Corner", 1 1/2" below surface of gravel road.  
Set Ottawa County Remon Tag & nail in West side of Power Pole N13°30'E 189.92'  
Set Ottawa County Remon Tag & nail in West side of Triple 9" Ash S19°W 23.99'  
Set Ottawa County Remon Tag & nail in SE side of 20" Pear Tree S57°30'W 73.82'  
SE concrete block corner, building to NW N42°30'W 100.42'  
Set Ottawa County Remon Tag & nail in West side of Wood Post N22°30'W 59.18'  
Centerline, gravel road North, 3'± East  
On occupation line South, ±  
Centerline, gravel road East & West, 2'± South

Signed by Donald W. Schiele

Date AUG. 20, 1996

Surveyor's Michigan License No. 23517

Section A., continued:

L.C.R.C. recorded in Liber 2, Page 253, 8-6-73

B-3 5/8" Rod Found

S.E.	71.15	8" Ash
S.W.	73.80	14" Pear Tree
N.W.	59.22	T.P.

L.C.R.C. recorded in Liber 4, Page 99, 8-13-80

B-3 Set Cast Iron Monument Inscribed "Section Corner"

8" Ash	SE	71.08
14" Pear Tree	SW	73.66
Gen. Street Sign	SSE	22.41
Wood Post	NW	59.26

SURVEY &  
REMONUMENTATION

OCT 07 1996

COMMISSION

\$ 11.00 CORNER  
\$ 1.00 PHOTO  
\$ 1.00 PHOTO