

FEB 24 2000

RECORDED

99 SEP -9 PM 12:15

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

| Ottawa (County) | Located In: | Corner Code # |
|---------------------------------------|-------------------|--------------------------------------------|
| 1. Public Land Survey | T 8N R 14W | B-7 (N $\frac{1}{4}$, 19) Polkton Twp. |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling In Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

Sam Schille
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Donald W. Schiele, in a field survey on Aug. 23, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | ● | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-7 1/4 corner common to Sections 18 & 19, Polkton Twp.

Original Government Corner Record:

Set qr section post
Post

W Ash 9 S60E 20
Beech 10 N43W 20

John Mullett, Deputy Surveyor
April 15, 1837

L.C.R.C. recorded in L.1, P.537, 7-24-72 by
C.P. Englert, Jr.:
1" Pinched Pipe

S.S.E. Twin Maple 81.25
North 20" Ash 33.53
South CL Pavement 17.70
N.E. 18" Maple 57.70

(SEE REVERSE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-7 Found Cast Iron Monument inscribed "Section Corner", 7" below ground level, and accepted as a careful and faithful perpetuation of the position of the original corner.

| | | |
|----------------------------------------------------|----------|-----------|
| Found nail & washer in South side of 26" Maple | N60°E | 57.19'(E) |
| Found nail in East side of Twin 11" Maple | S34°30'E | 81.70'(E) |
| Centerline 8" Ash (formerly Twin) | S02°E | 65.7'(E) |
| Centerline East & West asphalt road | South | 17.9' |
| Found nail & washer in East side of Telephone Pole | S03°W | 59.76'(E) |
| Found nail & washer in East side of 30" stump | N04°30'W | 33.11'(E) |



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-7 Cast Iron Monument inscribed "Section Corner", 7" below ground level.

| | | |
|-------------------------------------------------------------------|----------|-----------|
| Set Ottawa County Remon Tag & nail in SE side of 26" Maple | N60°E | 57.93'(E) |
| Set Ottawa County Remon Tag & nail in NE side of Twin 11" Maple | S34°30'E | 81.50'(E) |
| Set Ottawa County Remon Tag & nail in East side of Telephone Pole | S03°W | 59.94'(E) |
| Set Ottawa County Remon Tag & nail in SW side of 8" Pine | N37°30'W | 31.08'(E) |
| Centerline East & West asphalt road, 17.9' South | | |
| On occupation line to North | | |
| On fence remnant line to South | | |

\$11.00 CORNER
Receipt #56820

FILED APPROVED 8/30/99

Signed by

Donald W. Schiele

Date August 24, 1999

Surveyor's Michigan License No.

23517

Part A., continued:

L.C.R.C. recorded in L.4, P.251, 12-4-81 by Thomas E. Joiner:

B-7 Set Cast Iron Monument
31" Ash N 33.33
18" Maple NE 57.62
Tw. 6" Ash S 65.69
Tw. 8" Maple SE 81.70

Certified Survey Map of Ottawa County recorded in L.7, P.309, 12-28-90 by D.W. Schiele:

B-7 Found Cast Iron Monument
31" Ash North 33.33'
18" Maple NE 57.62'
8" Twin Maple SE 81.32'
6" Twin Ash South 65.70'

L.C.R.C. recorded in L.6, P.245, 1-25-93 by David E. Erickson:

B-7 Cast Iron Monument
N01W 33.13' N & W in E Side 30" Ash Stump
N64E 57.25' N & W in S Side 18" Maple
S31E 81.81' Nail in E Side Twin 12" Maple
S08W 60.14' N & T in E Side Telephone Pole
South 17.8' CL Cleveland Street

FEB 24 2000

SECTION