

SURVEY & REMONUMENTATION

JUN 28 1999

OTTAWA COUNTY REMONUMENTATION

RECORDED

98 NOV -4 PH 2: 30

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

[Signature]
REGISTER OF DEEDS
OTTAWA COUNTY, MI

SECTION

For corners in

OTTAWA

(County)

Located in:

Corner Code #

- | | | |
|------------------------------------|---|------------------|
| 1. Public Land Survey | T <u>8N</u> R <u>14W</u> | B-11 N1/4 corner |
| | T <u> </u> R <u> </u> | Sec 31 Polkton |
| | T <u> </u> R <u> </u> | Township |
| | T <u> </u> R <u> </u> | |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | |
| | S <u> </u> T <u> </u> R <u> </u> | |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | |
| | S <u> </u> T <u> </u> R <u> </u> | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randal J. Vugteveen, in a field survey on September 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	19	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11	●												
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

3-11 GLO John Mullett D.S.
April 1837 Set Post
7" Birch S84°W 22 Links
7" White Ash S48°E 26 Links

LCRC Liber 4, Page 245
Joiner Nov 1981
Set Cast Iron Monument
24" Maple NNE 22.50'
8" Ash North 31.57'
2" Pipe on Conc. Headwall WSW 73.80'
20" Maple ENE 78.77'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-11 Found Cast Iron Monument on Gravel Road under Construction 22" below surface

2" Pipe on Conc. Headwall WSW 73.80'
P.S. # 18987 Iron S0°E 33.00'


Accepted Cast Iron Monument as a careful and faithful perpetuation of the position of the original corner.

Set 3/4" X 19" Steel Bar with O.C.
Remonumentation cap on top of Cast Iron Monument Below upon request of Road Commission

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11 3/4" X 19" Steel Bar with O.C. Remon Cap on top of Cast Iron Monument

Centerline Gravel Road N0°E 0.00'
Set Remon Tag and Nail in W Side 8" Maple S07°E 36.74'
Set Remon Tag and Nail in E side 12" Poplar N13°E 44.92'
Set Remon Tag and Nail in N side Twin 14" ASH S68°E 92.16'
Set Remon Tag and Nail in S side 36" OAK N79°W 153.77'



\$9.00 CORNER
Receipt #18213
\$1.00 PHOTO
Receipt #18213

Signed by *[Signature]*
Surveyor's Michigan License No. 28429

Date OCTOBER 19, 1998

LIBER 004 PAGE 217