

SURVEY & REMONUMENTATION

OCT 07 1996

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>14W</u>	<u>C-8 (W. 1/4, 20)</u> <u>Polkton Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

96 AUG 26 PM 2:03

Elizabeth R. Sullivan
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Donald W. Schiele, in a field survey on August 19, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

C-8 1/4 corner common to Sections 19 and 20, Polkton Twp.
Original Government Corner Record: L.C.R.C. recorded in Liber 1, Page 537, 7-24-72
Beech 18 qr section corner R.R. Spike
18" Beech
John Mullett, Deputy Surveyor E.S.E. 25.14 36" Maple
April 14, 1837 S.E. 38.05 28" Cherry
N.W. 46.6 6" Maple

(SEE REVERSE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-8 Found Cast Iron Monument (broken) in Monument Box, 6 1/2" below surface of pavement, and accepted as a careful and faithful perpetuation of the position of the original corner.
Found nail & tag in South side of 38" Stump S85°E 24.15'
Found nail & tag in North side of 22" Triple Cherry S49°30'E 37.84'
Found nail in NW side of Telephone Pole S29°W 67.33'
Found PK nail in NW side of Telephone Pole S29°W 67.42'
Found nail in SW side of 6" Maple Stump N63°30'W 46.72'
Found nail in East side of 34" Cottonwood N12°30'W 115.32'

P.A. 345 OTTAWA COUNTY

PEER APPROVED 8-20-96

Gordon P. Redwood



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-8 Cast Iron Monument (broken) in Monument Box, 6 1/2" below surface of pavement.
Set Ottawa County Remon Tag & nail in SW side of 22" Triple Cherry S49°30'E 37.92'
Set Ottawa County Remon Tag & nail in SE side of Telephone Pole S29°W 67.47'
Set Ottawa County Remon Tag & nail in North side of 16" Maple N69°W 55.72'
Set Ottawa County Remon Tag & nail in East side of 34" Cottonwood N12°30'W 115.55'
Centerline asphalt road North & South, 0.2' East
On occupation & fence line East, ±
On occupation line West, ±

Signed by Donald W. Schiele Date Aug 20, 1996
Surveyor's Michigan License No. 23517

Section A., continued:

C-8

L.C.R.C. recorded in Liber 4, Page 286, 1-5-82

Set Cast Iron Monument

Tele. Pole SW 67.37

6" Maple NW 46.66

40" Maple NE 25.08

24" Cherry SE 38.03

L.C.R.C. recorded in Liber 6, Page 244, 1-25-93

Broken Cast Iron Monument in Monument Box

S80E 24.18' N & S in S Side 30" Maple Stump

S44E 37.88' N & S in N Side Triple 16" Cherry

S32W 67.51' PK in W Side Telephone Pole

N08W 115.43' N & S in E Side 28" Cottonwood

**SURVEY &
REMONUMENTATION**

OCT 07 1996

COMMISSION

\$ 11.00 CORNER
\$ 1.00 PHOTO
\$ 1.00 PHOTO