

**SURVEY &
REMONUMENTATION**

APR 25 1995

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:35

COMMISSION

For corners in

Ottawa
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>8N</u> R <u>14W</u>	<u>D-9 (N$\frac{1}{4}$, 29)</u>
	T _____ R _____	<u>Polkton Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Phyllis Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9		●										
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Donald W. Schiele in a field survey on November 19, 19 94
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-9 $\frac{1}{4}$ cor. common to Sections 20 & 29, Polkton Twp. L.C.R.C. recorded in Liber 1, Page 561, 8-21-72
Original Government Corner Record:
Or section post between sections 20 & 29 Found Stone - set Cast Iron Monument
Post inscribed "Ottawa Co. Sec. Cor."
Beech 18 S62E 60 P.P. N 33.56'
Do 15 N10E 17 18" Maple SE 42.55'
John Mullett, Deputy Surveyor NE Cor. Barn S 31.32'
April 14, 1837

(SEE REVERSE)

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-9 Found 6"-long piece of Cast Iron Monument, leaning. Established position of $\frac{1}{4}$ corner by using witnesses taken by us in 1985. Set $\frac{3}{4}$ " X 36" steel bar with Ottawa County Remon Cap 2" below surface and accepted as a careful and faithful perpetuation of the position of the original corner.

Found nail in West side of Power Pole	North	33.89'
Face of Power Pole	North	33.39'
NE corner, Barn foundation	South	31.49'
NW corner, Barn foundation	SW	43.59'
Section corner	West	2665.90'
Section corner	East	2662.41'


PA. 345 OTTAWA COUNTY
PEER APPROVED 11/21/94

Walter P. Nedrow

Note: This corner was positioned vertically to prepare for asphalt paving.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9 $\frac{3}{4}$ " X 36" steel bar with Ottawa County Remon Cap, 5" below surface in Monument Box.
Set Ottawa County Remon Tag & nail in East side of Power Pole North 33.80'
Set Ottawa County Remon Tag & nail in East side of Power Pole South 114.52'
NE corner, Barn foundation South 31.49'
Set Ottawa County Remon Tag & nail in NW side of Power Pole S51°W 121.91'
SE corner, foundation to House # 8417 N56°W 150.85'
On centerline Power Pole line North & South
On centerline asphalt road East & West



Signed by Donald W. Schiele

Date Nov. 21, 1994

Surveyor's Michigan License No. 23517

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

PART A. continued:

D-9

D.W. Schiele, 1985 (unrecorded)

Found Cast Iron Monument

Power Pole	North	33.92'
18" Maple	SE	43.93'
NE corner, Barn	South	31.52'
NW corner, Barn	SW	43.62'
Section corner	West	2665.89'
Section corner	East	2662.40'

120 #
9.00
051
2.00