

SURVEY & REMONUMENTATION

FEB 27 1998

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T 8N R 14W	E-2 (W $\frac{1}{4}$, 4) Polkton Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED

97 DEC -8 AM 11:33

Ray Hill
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Donald W. Schiele, in a field survey on November 19, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-2 1/4 corner common to Sections 4 and 5, Polkton Twp.
Original Government Corner Record: L.C.R.C. recorded in Liber 3, Page 120, 10-21-76:
Set qr section post E-2: Set railroad spike on centerline B.T. in line
Post with E-W fence
Sugar 9 S19W .11 "x" on N end concrete culvert E-SE 27.62'
Beech 9 N53E .25 Sq. spike in N side 5" Spruce W 38.51'
John Mullett, Deputy Surveyor Sq. spike in SW side 5" Maple N-NW 86.66'
April 13, 1837

(SEE REVERSE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-2 Found Cast Iron Monument inscribed "Section Corner" at surface level of asphalt road, and accepted as a careful and faithful perpetuation of the position of the original corner.
Centerline 18" dead Ash S87°30'E 64.6'±
Found "X" in North end of 12" Concrete Culvert S74°30'E 27.56'(E)
South end of 12" Concrete Culvert S47°30'W 37.29'(E)
Found nail in NE side of 10" Ash N22°W 86.62'(E)

PA. 345 OTTAWA COUNTY
PEER APPROVED *12-1-97*



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-2 Cast Iron Monument inscribed "Section Corner", at surface level of asphalt road.
Set Ottawa County Remon Tag & nail in North side of 10" Ash S89°30'E 31.72'(E)
"X" in North end of 12" Concrete Culvert S74°30'E 27.56'(E)
Set Ottawa County Remon Tag & nail in North side of 10" Ash N80°W 32.27'(E)
Set Ottawa County Remon Tag & nail in NE side of 10" Ash N22°W 86.62'(E)
On centerline asphalt road North & South
On occupation lines, ±, East & West

\$ 11.00 CORNER
\$ 2.00 PHOTO

Signed by Donald W. Schiele Date Nov. 26, 1997

Surveyor's Michigan License No. 23517

Part A., continued:

L.C.R.C. recorded in Liber 4, Page 285, 1-5-82:

E-2:	Set Cast Iron Monument	
SW	S. End Culv.	37.40
W	Tele. Sign	34.75
E	10" Ash	64.49
NW	6" Poplar	86.65

**SURVEY &
REMONUMENTATION**

FEB 27 1998

SECTION

1997 23. 24.

[Handwritten signature]