

# SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE** 94 DEC 14 AM 9:40  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

*Elizabeth Williams*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>14W</u>	E-5 (NW, 16) Polkton Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Donald W. Schiele, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

E-5 corner common to Sections 8, 9, 16 & 17, Polkton Twp.  
 Original Government Corner Record: L.C.R.C. recorded in Liber 4, Page 306, 4-1-82  
 Set corner post Sec. 8, 9, 16, 17 Set Cast Iron Monument  
 Post Power Pole NE 94.83  
 B Ash 10 S21W 11 Tele. Pole W 32.00  
 Do 9 N78E 18 6" Tree SW 58.04  
 John Mullett, Deputy Surveyor E. End 24" Culv. SE  
 April 12, 1837

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

E-5 Found Cast Iron Monument inscribed "Section Corner", 2" below surface in Monument Box, and accepted as a careful and faithful perpetuation of the position of the original corner.  
 Found "X" on East end of 24" Concrete Culvert S31°E 52.80'  
 Found PK nail in East side of Telephone Pole N83°W 31.84'

P.A. 345 OTTAWA COUNTY  
 PEER APPROVED 12/12/94



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E-5 Cast Iron Monument inscribed "Section Corner", 2" below surface in Monument Box.  
 Set Ottawa County Remon Tag & nail in NW side of Power Pole N43°E 46.43'  
 "X" on East end of 24" Concrete Culvert S31°E 52.80'  
 Set Ottawa County Remon Tag & nail in West side of 17" Maple S10°E 202.85'  
 Chiselled "X" on West end of 24" Concrete Culvert S21°W 55.00'  
 Set Ottawa County Remon Tag & nail in North side of Telephone Pole N83°W 32.12'  
 On centerline asphalt road North & South  
 On occupation lines East & West

Signed by Donald W. Schiele Date Dec. 12, 1994  
 Surveyor's Michigan License No. 23517