

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 10:02

Richard A. Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T 8N R 14W	E-7 (NW, 21) Polkton Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Donald W. Schiele, in a field survey on December 6, 19 94
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
E-7 corner common to Sections 16, 17, 20 & 21, Polkton Twp.
Original Government Corner Record: L.C.R.C. recorded in Liber 3, Page 241, 12-28-77
Set corner post Sec. 16, 17, 20, 21 Square iron from Michigan State Highway Plans
Post MSHD PK nail and tag in SE side P. Pole NE 49.90'
Elm 10 N30½E 70 PK nail in E side T. Pole NNW 76.85'
Pine 8 N17W 80 PK nail in W side P. Pole SSE 68.59'
John Mullett, Deputy Surveyor PK nail in N side T. Pole WSW 73.06'
April 12, 1837 N edge of N rail SSW 13.85'

(SEE REVERSE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-7 Found Cast Iron Monument inscribed "Section Corner", 4½" below surface in Monument Box,
and accepted as a careful and faithful perpetuation of the position of the original
corner.

Found PK nail & MSHD Tag in SE side of Power Pole	N38°E	49.91'
Found PK nail & MSHD Tag in West side of Power Pole	S15°30'E	68.53'
Found nail in North side of Power Pole	S15°30'E	68.07'
Found PK nail in East side of Guy Pole	S22°W	67.80'
Found PK nail in NE side of Telephone Pole	N26°W	76.96'



Madison P. Hedgewell PA. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-7 Cast Iron Monument inscribed "Section Corner", 4½" below surface in Monument Box.
Set Ottawa County Remon Tag & nail in NW side of Power Pole N38°E 50.04'
Set Ottawa County Remon Tag & nail in SW side of Power Pole S15°30'E 68.60'
Set Ottawa County Remon Tag & nail in SE side of Guy Pole S22°W 67.77'
Set Ottawa County Remon Tag & nail in NE side of Telephone Pole N26°W 77.01'
On centerline asphalt road to North
Centerline asphalt road to South, 2.5' West
Centerline asphalt road East & West, 1.9' South

Signed by Donald W. Schiele Date Dec. 12, 1994
Surveyor's Michigan License No. 23517

PART A. continued:

L.C.R.C. recorded in Liber 6, Page 53, 10-12-90
E-7

Set CIM

PK Nail in TP	NW	76.88'
PK Nail in PP	NE	49.89'
PK Nail in PP	SE	68.60'
PK Nail in Guy Pole	SSW	67.84'