

RECORDED

93 DEC 15 AM 9:27

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Phyllis Keltman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

Ottawa  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 8N R 14W E-9 (NW, 28)  
T \_\_\_\_\_ R \_\_\_\_\_ Polkton Twp.
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_ *See #1 pm*
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Donald W. Schiele, in a field survey on November 30, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- E-9 corner common to Sections 20, 21, 28 & 29, Polkton Twp.
- L.C.R.C. recorded in Liber 2, Page 123, 5-7-73
- 1" Iron Pipe
- SW 83.14' P.P.
- NE 41.30' F.P.
- NW 37.22' F.P.
- SE 39.70' Tel. Cable Marker
- L.C.R.C. recorded in Liber 4, Page 157, 4-1-8
- C.I.M.
- Power Pole SW 83.14'
- Fence Post SE 26.73'
- Wood Post NW 58.36'
- Telephone Pedestal NE 47.06'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-9 Found Cast Iron Monument with top broken off and accepted as a careful and faithful perpetuation of the position of the original corner.
- Found Telephone Pedestal NE 46.79'
- Found Telephone Cable Marker (bent) SE 35.3'±
- Found nail shaft in NE side of Fence Post SE 26.74'
- Found nail in SE side of Power Pole SW 83.11'


*Donald W. Schiele*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-9 Cast Iron Monument with top broken off 6" below surface.
- SW corner, Foundation to House # 7961
- Set Ottawa County Remon Tag & nail in South side of Power Pole N70°E 273.33' (E)
- Set Ottawa County Remon Tag & nail in NE side of Fence Post S78°E 180.19' (E)
- Set Ottawa County Remon Tag & nail in SE side of Power Pole S38°E 26.69'
- Set Ottawa County Remon Tag & nail in East side of Power Pole S51°W 83.10'
- Set Ottawa County Remon Tag & nail in East side of Power Pole N12°W 290.80' (E)
- Centerline gravel road to North, 1' East
- On Centerline gravel road East & West

Signed by Donald W. Schiele  
Surveyor's Michigan License No. 23517

Date DEC. 6, 1993



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 11, 1975  
REMOVED JAN., 1983