

OTTAWA COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:34

Robert A. Blom
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T 8N R 14W	F-9 (N $\frac{1}{4}$, 28) Polkton Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	<i>Seg #2 pm</i>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Donald W. Schiele, in a field survey on November 19, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 F-9 $\frac{1}{4}$ corner common to Sections 21 & 28, Polkton Twp.
 L.C.R.C. recorded in Remon Liber 1, Page 193, 12-15-93
 Set $\frac{3}{4}$ " X 36" solid bar with Ottawa County Remon Cap 7" below surface in place of $\frac{1}{2}$ " X 18" re-rod and broken Cast Iron Monument.
 Chiselled "X" on Northerly end of 18" Concrete Culvert N02°E 25.48'
 Set Ottawa County Remon Tag & nail in NE side of Power Pole S40°E 73.05'
 Set Ottawa County Remon Tag & nail in SE side of Power Pole S63°W 129.40'
 Set Ottawa County Remon Tag & nail in SW side of 3" Elm N13°W 55.97'
 Centerline ditch to North, 5' West. Centerline gravel road to South, 5' West.
 On centerlines asphalt road to East & gravel road to West.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 F-9 Found $\frac{3}{4}$ " X 36" solid bar with Ottawa County Remon Cap, 12" below surface.
 Found Ottawa County Remon Tag & nail in NE side of Power Pole S40°E 73.03'
 Found Ottawa County Remon Tag & nail in SE side of Power Pole S63°W 129.44'
 Found Ottawa County Remon Tag & nail in SW side of 3" Elm N13°W 55.95'
 Raised bar with Cap to 2" below gravel surface, adjusted to fit original witnesses, and accepted as a careful and faithful perpetuation of the position of the original corner.
 Note: This corner was raised to prepare for asphalt paving.

PA. 345 OTTAWA COUNTY
 PEER APPROVED 11/21/94

Madon D. Hedewell

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 F-9 $\frac{3}{4}$ " X 36" solid bar with Ottawa County Remon Cap, $\frac{4}{8}$ " below surface in Monument Box.
 Ottawa County Remon Tag & nail in NE side of Power Pole S40°E 73.05'
 Ottawa County Remon Tag & nail in SE side of Power Pole S63°W 129.40'
 Ottawa County Remon Tag & nail in SW side of 3" Elm N13°W 55.97'
 Chiselled "X" in Northerly end of 54" Concrete Culvert N05°W 31.48'
 Centerline ditch to North, 5' West
 Centerline gravel road to South, 5' West
 On centerline asphalt road East & West



Signed by Donald W. Schiele Date Nov. 21, 1994
 Surveyor's Michigan License No. 23517