

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Donald W. Schiele
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in
Ottawa

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 8N R 14W F-11 (S $\frac{1}{4}$, 28)
T _____ R _____ Polkton Twp.
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Donald W. Schiele, in a field survey on December 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- F-11 corner common to Sections 28 & 33, Polkton Twp.
L.C.R.C. recorded in Liber 2, Page 785, 6-25-75 L.C.R.C. recorded in Liber 4, Page 229, 10-22-81.
- 1/2" Iron C.I.M.
- PK in sde P. Pole SE 72.01' Telephone Pole SE 71.98'
- PK in sde P. Pole WSW 169.87' R.R. Tie Fence Post Cor. NE 55.00'
- Cut mark in W end of 42" CMP NNW 59.99' Mark in W. end 42" CMP. NW 60.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F-11 Found Cast Iron Monument in Monument Box and accepted as a careful and faithful perpetuation of the position of the original corner.
- Found cut mark in East end of 42" corrugated metal pipe NE 59.52'
- Found PK nail in top of RR Tie fence post corner leaning NE NE 56.63'
- Found PK nail in SW side of Power Pole SE 73.31'
- Found PK nail in North side of Power Pole WSW 192.88' (E)
- Found cut mark in West end of 42" corrugated metal pipe NW 59.98'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-11 Cast Iron Monument in Monument Box 4" below surface.
- Cut mark in East end of 42" corrugated metal pipe N24°E 59.52'
- Set Ottawa County Remon Tag & nail in NW side of 16" Apple N44°E 158.73' (E)
- Set Ottawa County Remon Tag & nail in SW side of Power Pole S43°E 73.30'
- Set Ottawa County Remon Tag & nail in North side of Power Pole S75°W 192.86' (E)
- Cut mark in West end of 42" corrugated metal pipe N23°W 59.98'
- Centerline gravel road to North, 2' West
- On centerline gravel road South
- On centerline asphalt road East & West

Signed by Donald W. Schiele

Date DEC. 6, 1993

Surveyor's Michigan License No. 23517

