

**SURVEY &
REMONUMENTATION**

APR 05 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Ottawa _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T8N R14W T _____ R _____ T _____ R _____ T _____ R _____	G-6 E 14/ cor. Sec. 16, Polkton Twp.
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____

RECORDED
95 DEC 12 AM 11:50

Richard R. Kishner
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, Steve Lampen _____, in a field survey on November 15, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-6 GLO Survey Notes 1837, Surveyor - John Mullett Set post 10" Beech S 5° E 24 links 6" Beech N 7° W 9 links	LCRC L 4-P 221 Oct. 9, 1981 Found "T" iron on centerline Nail in 14" Maple NNW 51.62' Nail in 14" Maple NW 33.76' Nail in power pole SW 63.68'	LCRC L 6-P 27 Jan. 3, 1990 Found "T" iron and stone Set cast iron monument 12" Maple NW 33.74' Power pole SW 63.60' 1/2" rod SE 30.01' 1/2" rod NE 30.02'
---	--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-6
Found cast iron monument and accepted it as a careful and faithful perpetuation of the position of the original corner.

12" Maple NW 33.74'	Nail in 14" Maple NNW 51.62'
Power pole SW 63.60'	Nail in 14" Maple NW 33.76'
1/2" rod SE 30.01'	Nail in power pole SW 63.68'
1/2" rod NE 30.02'	

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/20/95

Richard P. Newell
RPN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6
Cast iron monument
Set O. C. Remonumentation tag & nail in ENE side 17" Maple N 40° W 33.82'
Set O. C. Remon. tag & nail in NW side Power pole S 40° W 63.81'
Witness iron & cap #16042 N 36° E 30.02'
Witness iron & cap #16042 S 30° E 30.01'



Signed by Steven Lampen Date November 17, 1995

Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 24, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983