

**SURVEY & REMONUMENTATION**

APR 05 1996

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**

**COMMISSION** Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T8N R14W	G-8
	T _____ R _____	E 1/4 cor. Sec.
	T _____ R _____	21, Polkton Twp.
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

**RECORDED**  
95 DEC 12 AM 11:50  
*Richard Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI  
**Register of Deeds Stamp & File Number**

I, Steven Lampen, in a field survey on November 17, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

G-8 GLO Survey Notes 1837, Surveyor - John Mullett Set post 11" Maple S 11° E 45 links 10" Beech N 1° W 23 links	LCRC L 2-P 499 May 29, 1974 Found stone & plow point Set angle iron Power pole SE 72.49' Street sign N 24.06' MBT ped. SW 57.06'	LCRC L 2-P 625 Oct. 9, 1974 Found angle iron 30" Oak SSW 158.71' 22" Maple NNW 142.74'	LCRC L 2-P 731 Jan. 14, 1975 Set cast iron mon. in place of stone 18" Maple SSW 205.70' 20" Maple NNW 143.00'
---	--	--	---

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

G-8  
Found cast iron monument  
Nail SE face 24" Maple AZ 349° 143.00'

PA. 345 OTTAWA COUNTY  
PEER APPROVED 11/20/95

*Richard D. Redwood*  
*RDR*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-8 Cast iron monument Ottawa County Remonumentation nail & tag NW face 24" Maple O. C. Remon. nail & tag E face 24" Maple "X" cut in top of S end 12" CMP drain culvert O. C. Remon. nail & tag in top of corner Split rail fence post	AZ 188° 206.01' AZ 143° 143.96' AZ 8° 135.48' AZ 15° 126.15'
---	---



Signed by Steven Lampen  
Surveyor's Michigan License No. 37279

Date November 17, 1995