

SURVEY &
REMONUMENTATION

APR 05 1996

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T8N R14W	H-9
	T R	S 1/4 cor. Sec.
	T R	22, Polkton Twp
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED
95 DEC 12 AM 11:51
Robert Caldwell
REGISTER OF DEEDS
OTTAWA COUNTY, MI
Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Steven Lampen, in a field survey on November 17, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-9	LCRC L 2-P 127	LCRC L 2-P 385
GLO Survey Notes	May 7, 1973	Nov. 26, 1973
1837, Surveyor - John Mullett	1" pipe in mon. box	Monument box
Set post	Telephone pole NE 69.3'	Guy pole NE 67.66'
9" Maple S 40° E 22 links	Power pole SW 61.52'	P.K. at centerline "X" S 17.56'
9" Maple N 65° W 22 links	Telephone pole SE 112.65'	Power pole SW 61.52'

See page 2

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-9		
Found 3/4" iron in monument box		
P.K. in centerline joint of Randall Street old US-16	AZ 180°	17.51'
SE corner of brick building	AZ 323°	166.31'
Centerline top of hydrant	AZ 233°	87.65'

Replaced 3/4" iron in monument box with standard Ottawa County Remonumentation iron and cap and accepted it as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 11/20/95

Robert D. Newell

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-9		
Ottawa County Remonumentation iron and cap		
O. C. Remon. tag & nail in NW face power pole	AZ 42°	60.65'
"X" cut in top of NW bolt of sign pedestal	AZ 142°	91.61'
"X" cut in top of N spigot of hydrant	AZ 233°	87.40'
SE corner of building	AZ 323°	166.31'
P.K. in centerline joint of Randall St. (old US-16)	AZ 180°	17.51'



Signed by Steven Lampen Date November 17, 1995
Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1982
ADAPTED FOR WORD PROCESSING MARCH, 1993

A. (Cont'd)

H-9

LCRC L 4-P 46

April 9, 1980

Iron in Mon. box

Guy pole

Power pole

NW cor. brick gas station SE 147.72'

SE corner brick building N 50° W 166.40'

Centerline joint old US-16 S 17.33'

LCRC L 5-P 205

May 3, 1985

3/4" iron in mon. box

Guy pole

NW cor. brick gas station NE 69.40'

SE cor. brick building SE 147.72'

Centerline top hydrant NW 166.49'

SW 87.79'

\$ 11.00 CORNER
\$ 25.00 PHOTO