

**SURVEY &  
REMONUMENTATION**

**FEB 27 1998**

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

For corners in

OTTAWA

(County)

Located In:

Corner Code #

- |                                       |              |               |  |
|---------------------------------------|--------------|---------------|--|
| 1. Public Land Survey                 | T <u>8</u> N | R <u>14</u> W | H-13, S1/4 cor.,<br>Sec.34, Polkton<br>Twp |
|                                       | T ___ R ___  |               |  |
|                                       | T ___ R ___  |               |  |
|                                       | T ___ R ___  |               |  |
| 2. Property Controlling<br>in Section | S ___ T ___  | R ___         |  |
|                                       | S ___ T ___  | R ___         |  |
| 3. Miscellaneous<br>Property in Sec.  | S ___ T ___  | R ___         |  |
|                                       | S ___ T ___  | R ___         |  |

**RECORDED**

97 DEC -8 AM 11:28

*[Signature]*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Randal J. Vugteveen, in a field survey on November 21, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

**A. Description of original monument and accessories and/or subsequent restoration:**

- |  |  |  |
|--|--|--|
| H-13<br>G.L.O. survey notes 1837 surveyor John Mullett<br>Set quarter section post<br>9" ironwood N17°E 16 links<br>11" Beech N77°W 37 links | L.C.R.C. Liber 3 Page 139 9-17-76<br>Found 1' iron in monument box<br>NE 55.85' power pole<br>SE 45.0' street sign | L.C.R.C. Liber 5 Page 35 1-24-83<br>Found 1' iron in monument box<br>NE 55.88' PK in power pole 3' above ground<br>SE 45.24 centerline street sign<br>SW 56.71' PK in fence corner<br>E 2.6' to centerline crack |
|--|--|--|


**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- H-13 Found cast iron Ottawa County monument in monument box
- |   |  |
|---|--|
| Found PK nail SE face power pole AZ 56° 55.87'<br>Centerline bit road North & South (crack) East 2.9' | Accepted position of cast iron monument as a careful perpetuation of the position of the original corner |
|---|--|

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- H-13 Ottawa County Cast Iron Monument in Monument Box
- Set Ottawa County Remon tag & nail SE side power pole AZ 58° 55.86'
  - Set Ottawa County Remon tag & nail NE side power pole (6.5' above ground level) AZ 162° 162.47'
  - Set red Nederveld Assoc. capped rebar AZ 299° 56.96'
  - Set red Nederveld Assoc. capped rebar AZ 241° 56.59'
  - Centerline North-South road East 3'
  - Centerline East-West road South 1.5'

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 12/1/97



\$ 1.00 PHOTO

Signed by [Signature]  
Surveyor's Michigan License No. 28429

Date Dec 1, 1997