

SURVEY & REMONUMENTATION

RECORDED

DEC 01 1993

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

93 NOV 11 AM 11:55

COMMISSION

Phyllis Holman
**REGISTER OF DEEDS
OTTAWA COUNTY, MI**

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>14W</u>	<u>I-4 (E 1/4, 10)</u> <u>Polkton Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald W. Schiele, in a field survey on October 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-4 corner common to Sections 10 and 11 Polkton Twp.			
L.C.R.C. recorded in Liber 5, Page 353, C.I.M. 12-06-88.	PK Nail in 15" R. Pine	WNW. 50.95	L.C.R.C. recorded in Liber 4, Page 109, 10-14-80. C.I.M. Inscribed "Section Corner"
NE Cor Wood Garage	NW. 50.31	10" Black Cherry	NW. 42.84
PK Nail in 13" B. Cherry	NE. 51.75	28" Oak	ESE. 23.38
PK Nail in 3" Oak	SE. 43.69		SSE. 86.96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-4 Found C.I.M. inscribed "Section Corner" 4" below surface in Monument Box and accepted as a careful and faithful perpetuation of the position of the original corner.

Found PK nail in NW side of 13" Black Cherry	NE	51.69'
Found PK nail in NE side of 5" Oak	SE	43.69'
Centerline 16" Red Pine	WNW	50.75'
SE corner Wood Garage	NW	42.89'
NE corner Wood Garage	NW	50.32'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-4 Cemented 2" dia. aluminum Ottawa Co. Remon. Marker #21272 with 3/8" long Steel Bar in Monument Box over C.I.M.

Set Ottawa County Remon Tag & nail in NW side of 13" Black Cherry	N57°E	51.70'
Set Ottawa County Remon Tag & nail in NE side of 5" Oak	S56°E	43.66'
Set Ottawa County Remon Tag & nail in South side of 16" Red Pine	N80°W	50.85'
SE corner Wood Garage	N73°W	42.89'
NE corner Wood Garage	N53°W	50.32'

On Centerline asphalt road North and South

Signed by Donald W. Schiele
Surveyor's Michigan License No. 23517

Date: 10-18-93

No. _____

REGISTERED LAND SURVEYOR

STATE OF MICHIGAN

Donald W. Schiele

Land Surveyor

APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983