

SURVEY & REMONUMENTATION

APR 05 1996

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in Ottawa (County) Located In: Corner Code #

1. Public Land Survey T8N R14W I-6
 T R E 1/4 cor. Sec.
 T R 15, Polkton Twp.
 T R
 T R

2. Property Controlling in Section S T R
 S T R
 S T R

3. Miscellaneous Property in Sec. S T R
 S T R

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

RECORDED

95 DEC 12 AM 11:51

Richard R. Williams
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Steven Lampen, in a field survey on November 17, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-6
 1837, Surveyor - John Mullett LCRC L 2-P 265 LCRC L 4-P 110
 Set post Aug. 6, 1973 Oct. 14, 1980
 10" Cherry N 4° W 35 links Found 3" iron Found 3" iron
 9" Linden N 7° E 45 links 30" Sycamore NE 60.69' Set cast iron mon.
 12" Basswood SE 70.82' 30" Sycamore NE 60.69'
 NW cor. bridge abut. SSW 90.55' 12" Basswood SSE 70.82'
 9" tree SE 59.33'
 NW cor. bridge abut. SSW 90.55'

LCRC L 5-P 320
 Aug. 9, 1988
 Set C.I.M.
 TP SW 30.00'
 10" Elm SE 59.38'
 32" Sycamore NE 60.21'
 13" Poplar E 50.84'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6
 Found cast iron monument and accepted it as a careful and faithful perpetuation of the position of the original corner.

TP SW 30.00'
 10" Elm SE 59.38'
 32" Sycamore NE 60.21'
 13" Poplar E 50.84'
 NW cor. bridge abut. SSW 90.55'

P.A. 345 OTTAWA COUNTY
 PEER APPROVED 11/20/95

Richard D. Redwood
 RDR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6
 Cast iron monument
 Set O. C. Remonumentation tag & nail in NNE side power pole N 70° W 39.61'
 Set O. C. Remon. tag & nail in side 30" Sycamore N 56° E 60.58'
 Set O. C. Remon. tag & nail in side Elm S 54° E 59.19'
 NW corner bridge culvert S 13° W 92.45'



Signed by Steven Lampen

Date November 17, 1995

Surveyor's Michigan License No. 37279