

**SURVEY &
REMONUMENTATION**

APR 24 1995

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 15 AM 11:47

For corners in **COMMISSION**

Deborah R. Anderson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>14W</u>	<u>I-8 (W$\frac{1}{4}$, 23)</u> <u>Polkton Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald W. Schiele, in a field survey on December 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-8 $\frac{1}{4}$ corner common to Sections 22 & 23, Polkton Twp.	L.C.R.C. recorded in Liber 3, Page 245, 12-29-77	L.C.R.C. recorded in Liber Page 46, 4-9-80
Original Government Corner Record:	Angle Iron	"L" Iron
Set qr section post between Sec. 22 & 23	N55°W 69.04' Spike in P. Pole	C/L P & T pole
Post	N75°E 65.00' Center of Man Hole	N60°W 69.48'
Elm 11 S39E 11	S 2°E 30.15' Spike in P. Pole	C/L top hyd N45°W 48.10'
B Ash 11 S29W 19	N40°W 48.18' Center of Fire Hydrant	C/L St. sign post
John Mullett, Deputy Surveyor		N75°E 95.40'
April 9, 1837		SE cor conc. blk. bldg.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
I-8 Found 24"-long Angle Iron, 3" below surface, and _____ accepted as a careful and faithful perpetuation of the position of the original corner.

Centerline Manhole Cover	N71°E	64.97'
SE corner, Concrete Block Building	N83°30'W	159.71'
Found nail in East side of Power Pole	N59°W	69.04'
Found nail in SW side of Power Pole	N59°W	69.47'
On centerline asphalt roads North, South & East		

PA. 345 OTTAWA COUNTY

PEER APPROVED

12/12/94
Donald D. Nelson



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I-8 Removed 24"-long Angle Iron and replaced with 3/4" X 24" Steel Bar with Ottawa County Remon Cap, 2 1/4" below surface in Monument Box.

Set Ottawa County Remon Tag & nail in SE side of 14" Poplar	N64°E	108.07'
Set Ottawa County Remon Tag & nail in SW side of 10" Twin Ash	S49°30'E	81.18'
Centerline Fire Hydrant	S42°W	42.66'
SE corner, Concrete Block Building	N83°30'W	159.71'
Set Ottawa County Remon Tag & nail in SW side of Power Pole	N59°W	69.42'
On centerline asphalt roads North, South & East		

Signed by Donald W. Schiele Date Dec. 12, 1994

Surveyor's Michigan License No. 23517