

FEB 24 2000

RECORDED

99 JUL 30 PM 12:26

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Randy S. Vugteveen
REGISTER OF DEEDS
OTTAWA COUNTY, MI

SECTION

For corners in
OTTAWA

	Located In:	Corner Code #
1. Public Land Survey	T 8N R 14W	I-10 W 1/4 Cor Sec 26 Polkton Twp
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randal J. Vugteveen, in a field survey on March 16, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27	▲	26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-10 GLO April 1837
John Mullett D.S.
Set quarter sec. post
11" hemlock S71°W 10 links
8" hemlock N71°E 06 links

I-10 Liber 1 Page 713
Englert 1972
"T" iron
N21.8' sign post
NE 25.85' sign post
S. 28.52' 4" W. cherry

I-10 Liber 4 page 305
Joiner 1982
Set cast iron monument
Fence post north 47.53'
28" maple East 122.75'
2" elm south 9.99'
Cor. fence post N.W. 132.98'
MSHD 1/4 cor 113.65' south of CL construction I-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10 found cast iron monument

Fence post North 47.0'
Center of median extended West I-96 113.5' +/-

Accepted Cast Iron Monument as a careful and faithful perpetuation of the position of the original corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10 Cast Iron Monument

Center 4" fence post to gate North 43.29'
Center 2" anchor fence post N60°W 134.24'
Set Ottawa Co. remon tag and Tag in E. side 4" X 6" wood post to speed limit sign N19°W 84.05'
Set Ottawa Co. remon tag and Nail in 8" elm N87°E 246.30'
Center of E. bound I-96 North 118.0'



\$9.00 DINNER
Receipt #52399

Signed by *Randal J. Vugteveen*
Surveyor's Michigan License No. 28429

Date MARCH 16, 1999