

**SURVEY &
REMONUMENTATION**

NOV 10 1993

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

1993 SEP 29 PM 3:14

For corners in

<u>Ottawa</u> <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>14W</u>	<u>J-3 (N 1/4, 11)</u> <u>Polkton Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Debbie Johnson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3									●			
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Donald W. Schiele, in a field survey on Sept. 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-3 corner common to Sections 2 and 11 Polkton Twp.
L.C.R.C. recorded in Liber 4, Page 112
C.I.M. Inscribed "Section Corner"
Power Pole NW. 27.15
Cen. Gravel Road N. 2'
10" Elm SSE. 36.35
8" Elm ESE. 76.20

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-3
Found C.I.M. Inscribed "Section Corner" leaning approximately 3" WNW and accepted as a careful and faithful perpetuation of the position of the original corner.
Found nail and tag #18435 in SE side of Power Pole NE 27.18'
(also found 2 other carpenter's nails and a concrete nail in SE side of Pole)
CL East and West gravel road North 2'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-3
C.I.M. leaning approximately 3" WNW 6" below surface
Set nail and Ottawa Co. re-mon. tag in SE side of Power Pole N21°E 27.24'
Set nail and Ottawa Co. re-mon. tag in NE side of 7" Elm S25°E 34.74'
Set nail and Ottawa Co. re-mon. tag in West side of Twin 6' Elm S3°E 25.46'
Set nail and Ottawa Co. re-mon. tag in North side of Power Pole S83°W 291.95' (E)
CL East and West gravel road North 2'
North and South lines of occupation East 3'±

Signed by Donald W. Schiele Date Sept. 20, 1993
Surveyor's Michigan License No. 23517

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1992
REVISED MAY 14, 1992
23

