

**SURVEY & REMONUMENTATION**

APR 25 1995

OTTAWA COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:34

COMMISSION

*Polycia Robinson*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

or corners in

Ottawa  
 (County)

Located In:

Corner Code #

Public Land Survey	T	8N	R	14W	J-7 (N $\frac{1}{4}$ , 23)
	T		R		Polkton Twp.
	T		R		
	T		R		
Property Controlling in Section	S		T	R	
Miscellaneous	S		T	R	
Property in Sec.	S		T	R	

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Donald W. Schiele, in a field survey on November 18, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

-7 $\frac{1}{4}$ corner common to Sections 14 & 23, Polkton Twp.	L.C.R.C. recorded in Liber 1, Page 201, 12-23-71	L.C.R.C. recorded in Liber 2, Page 349, 10-31-73
Original Government	PK in centerline road	Set $\frac{1}{2}$ " iron
Corner Record:	CP Pole N42°W 37.77'	St. sign N 2°W 21.50'
Lock 20 qr section	MBT Pole S33°E 61.80'	SW cor. brick porch
Corner between Sec. 14 & 23	SW Cor Porch N28°E 76.25'	N30°E 76.2'
Lock 20	NE Cor Hse Fnd S48°W 82.18'	NE cor. house
(no ties taken)		S40°W 82.0'
John Mullett, Deputy Surveyor		
April 9, 1837	(SEE REVERSE)	

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

-7 Found 4 PK nails at edge of Storm Manhole Cover. Intersected lines between opposite nails to establish location of  $\frac{1}{4}$  corner on Manhole Cover. Accepted intersection point as a careful and faithful perpetuation of the position of the original corner.

SW corner, brick porch to House # 375	N20°30'E	76.15'
Centerline Fire Hydrant	S65°E	53.52'
Found PK nail & tag in NE side of Telephone Pole	S41°E	40.85'
Found nail in SW side of Telephone Pole	S22°E	62.35'
NE corner, foundation to House # 787	S36°W	82.00'
Found nail & tag in NE side of Power Pole	N53°W	37.88'



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-7 Intersection of lines between opposite PK nails at edge of Storm Manhole Cover establishes $\frac{1}{4}$ corner on Manhole Cover.		
SW corner, brick porch to House # 375	N20°30'E	76.15'
Centerline Fire Hydrant	S65°E	53.52'
Set Ottawa County Remon Tag & nail in West side of Telephone Pole	S22°E	62.35'
NE corner, foundation to House # 787	S36°W	82.00'
Set Ottawa County Remon Tag & nail in SW side of Power Pole	N53°W	38.16'
Centerline asphalt road South, 1' West		
Centerline asphalt road East & West, 1' North		

PA. 345 OTTAWA COUNTY

PEER APPROVED 11/21/94

Signed by Donald W. Schiele

Date Nov. 21, 1994

Surveyor's Michigan License No. 23517

PART A. continued:

L.C.R.C. recorded in Liber 6, Page 222, 6-19-92

J-7

Found 4 PK nails at edge of storm MH - intersected lines to establish temp. point on MH cover.

NE cor of hse fndn	SW	82.01'
Fd nail & tag in NE sde P. Pole	NW	37.88'
Fd PK nail in NE sde T. Pole	SE	40.86'
SW cor of brick porch	NNE	76.15'
C/L top of fire hyd.	ESE	53.52'

L.C.R.C. recorded in Liber 6, Page 229, 8-13-92

J-7

Found 4 PK nails at edge of MH - intersected lines between nails to set temp. point in MH cover.

NE cor hse fndn.	SW	82.01'
Fnd nail & tag in NE sde P. Pole	NW	37.88'
Fnd PK nail in NE sde T. Pole	SE	40.86'
SW cor of brick porch	NNE	76.15'
C/L top of fire hydrant	ESE	53.52'