

# SURVEY & REMONUMENTATION

APR 25 1995

## OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:34

COMMISSION

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>14W</u>	<u>J-11 (N<math>\frac{1}{4}</math>, 35)</u> <u>Polkton Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*Register of Deeds*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald W. Schiele, in a field survey on November 17, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
J-11  $\frac{1}{4}$  corner common to Sections 26 & 35, Polkton Twp.

Original Government

L.C.R.C. recorded in Liber 1,

L.C.R.C. recorded in Liber 1,

Corner Record:

Page 713, 10-27-72

Page 773, 12-4-72

Set qr section post on true line between Sec. 26 & 35.

Boat Spike & Hoe

Fd. Boat Spike & Hoe

Post

N.W. 71.50 T.P.

N.W. 71.50 T.P.

Beech 7 S60E 20

S.W. 115.11 P.P.

S.W. 115.11 P.P.

Ironwood 6 N19W 24

S.E. 45.22 St. Sign

S.E. 45.22 St. Sign

John Mullett, Deputy Surveyor

(SEE REVERSE)

April 9, 1837

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-11 Found 2-3/4" dia. Cast Iron Monument (broken), 7" below surface in Monument Box, and accepted as a careful and faithful perpetuation of the position of the original corner.

Centerline Fire Hydrant N46°E 40.52'

Found nail in SW side of Power Pole S57°E 169.45'(E)

Centerline Street Sign S50°E 45.32'

Found nail in SW side of Telephone Pole N68°W 71.79'

Found nail in SE side of Telephone Pole N68°W 71.42'

P.A. 345 OTTAWA COUNTY

PEER APPROVED 11/21/94

*Donald P. Newbold*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11 Broken 2-3/4" dia. Cast Iron Monument, 7" below surface in Monument Box.

Centerline Fire Hydrant N46°E 40.52'

Set Ottawa County Remon Tag & nail in SW side of Guy Pole S39°30'E 43.63'

Set Ottawa County Remon Tag & nail in SE side of Power Pole S21°W 98.60'

Set Ottawa County Remon Tag & nail in NW side of Power Pole S46°W 48.90'

Set Ottawa County Remon Tag & nail in SW side of Telephone Pole N68°W 71.67'

Centerline gravel road North, 2' East


Centerline gravel road South, 3' East

Centerline asphalt road East & West, 1' South

Signed by Donald W. Schiele

Date Nov. 18, 1994

Surveyor's Michigan License No. 23517



FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS AND LAND OFFICIALS, 1975

PART A. continued:

L.C.R.C. recorded in Liber 5, Page 22, 3-4-83  
J-11

boat spike

NW 71.50' to nail in face of TP

SE 45.22' to street sign

NE 40.56' to C/L top of hydrant

L.C.R.C. recorded in Liber 5, Page 128, 6-27-84  
J-11

Set C.I.M.

HYD NE 40.52'

PP NW 71.37'

TP SW 115.18'

TP SE 164.51'