

# SURVEY & REMONUMENTATION

APR 25 1995

## OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:34

For corners **COMMISSION**

*Richard L. Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T 8N R 14W	J-13 (S $\frac{1}{4}$ , 35) Polkton Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald W. Schiele, in a field survey on November 17, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
J-13 South  $\frac{1}{4}$  corner, Section 35, Polkton Twp.

Original Government Corner Record:	L.C.R.C. recorded in Liber 4, Page 231, 10-22-81	L.C.R.C. recorded in Liber 5, Page 27, 3-4-83
W Ash 26 in dia for qr sec cor tree	Set Cast Iron Monument	Cast monument
26" White Ash (no ties taken)	Telephone Pole NE 82.14	NE 82.14' to T.P.
John Mullett, Deputy Surveyor	Street Sign East 29.90	E 29.90' to Street sign
March 13, 1837	R.R. tie Fence Cor. NW 30.57	NW 30.57' to nail & flag in R.R. tie fence cor.
	Fence Post SE 36.44	SE 36.44' to PK in W side of fence post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
J-13 Found Cast Iron Monument inscribed "Section Corner", 6" below surface of gravel road, and accepted as a careful and faithful perpetuation of the position of the original corner.

Found PK nail in SW side of Light Pole	N54°30'E	82.16'
Centerline Street Sign	N81°E	29.84'
Found PK nail in NW side of Fence Post	S71°E	36.54'
Found PK nail & tag in SW side of Power Pole	N47°W	74.43'

P.A. 345 OTTAWA COUNTY

PEER APPROVED 11/21/94  
*Robert D. Newbold*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
J-13 Cast Iron Monument inscribed "Section Corner", 6" below surface of gravel road.

Set Ottawa County Remon Tag & nail in NW side of Light Pole	N54°30'E	82.47'
Set Ottawa County Remon Tag & nail in NE side of corner Fence Post	S67°E	31.73'
Set Ottawa County Remon Tag & nail in SW side of 9" Spruce	S25°30'E	71.73'
Set Ottawa County Remon Tag & nail in SW side of Power Pole	N47°W	74.37'
Centerline gravel road North & South, 3' West		
On centerline gravel road to West		
On occupation line to East		

Signed by Donald W. Schiele  
Surveyor's Michigan License No. 23517

Date Nov. 18, 1994

