

**SURVEY &
REMONUMENTATION**

DEC 01 1993

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 NOV 11 AM 11:55

Richard Chubb
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in **COMMISSION**
Ottawa

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>14W</u>	<u>K-3 (NE, 11)</u>
	T _____ R _____	<u>Polkton Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Donald W. Schiele, in a field survey on November 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-3 corner common to Sections 1, 2, 11 and 12 Polkton Twp.		L.C.R.C. recorded in Liber 2, Page 783,		L.C.R.C. recorded in Liber 3, Page 233, 12-21-77.	
Iron Bar	SW. 92.27'	5-5-75.	C.I.M. Inscribed "Ottawa County Section Corner"	SE Building Corner	NW. 98.82
P. Pole	NW. 98.80'		Power Pole	SW. 92.25	
SE. Bldg. Cor.	NE. 41.40'		PK in Fence Post	W. 66.88	
St. Sign			PK in Fence Post	WNW. 70.70	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-3 Found C.I.M. inscribed "Ottawa County Section Corner" in Monument Box and accepted as a careful and faithful perpetuation of the position of the original corner.

Found double-headed nail in NW side of Power Pole	SW	92.30'
Found Tag # 14091 and nail in NW side of Power Pole	SW	92.29'
Found PK nail in SW side of Fence Post	NW	66.99'
SE Building Corner	NW	98.73'


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-3 C.I.M. inscribed "Ottawa County Section Corner" 7" below surface in Monument Box.

Set Ottawa County Remon Tag & nail in East side of Service Pole	N12°E	241.19'
Set Ottawa County Remon Tag & nail in NW side of Power Pole	S38°W	92.30'
Set Ottawa County Remon Tag & nail in North side of Corner Fence Post	S66°W	64.62'
SE Building Corner	N31°W	98.73'

On Centerline asphalt road North and South
On Centerline gravel road West
Centerline gravel road East 2' North

Signed by Donald W. Schiele Date Nov. 8, 1993
Surveyor's Michigan License No. 23517



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
REVISED JAN., 1983