

**SURVEY &
REMONUMENTATION**

RECORDED

93 NOV 11 AM 11:55

DEC 01 1993

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Donald W. Schiele
REGISTER OF DEEDS
OTTAWA COUNTY, MI.

For corners in **COMMISSION**

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>8N</u> R <u>14W</u>	<u>K-5 (SE, 11)</u> <u>Polkton Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald W. Schiele, in a field survey on October 28, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
K-5 corner common to Sections 11, 12, 13 and 14 Polkton Twp.
T.T.R.C. recorded in Liber 3, Page 237, 12-21-77.
C.I.M. Inscribed "Ottawa County Section Corner"
Screw in Hub NE. 59.73
Nail & Tag in Guy Pole SE. 71.81
PK in Power Pole SW. 65.84

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-5 Found C.I.M. inscribed "Ottawa County Section Corner" in Monument Box and accepted as a careful and faithful perpetuation of the position of the original corner.

Found PK nail in NE side of Power Pole	SE	57.72'
Found PK nail in SE side of Power Pole	SW	66.41'
Found PK nail in East side of Power Pole	SW	65.89'


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5 C.I.M. 8" below surface in Monument Box

Set Ottawa County Remon Tag & nail in NE side of Power Pole	S51°E	57.72'
Set Ottawa County Remon Tag & nail in SE side of Power Pole	S53°W	66.41'
Set Ottawa County Remon Tag & nail in North side of Power Pole	S82°W	230.62' (E)
Set Ottawa County Remon Tag & nail in side of Guy Pole	N60°W	61.05'

On Centerline asphalt road North and South
On Centerline gravel road East and West

Signed by Donald W. Schiele Date 10-30-93
Surveyor's Michigan License No. 23517



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 27, 1975
REVISOR JAN., 1983