

JEC 05 2000

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T 8N R 14W	K-6 (E. 1/4, 14)
	T R	Polkton Twp.
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

96 NOV 16 11:11:21

REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald W. Schiele, in a field survey on September 16, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
K-6 1/4 corner common to Sections 13 & 14, Polkton Twp.

Original Government Corner Record:	L.C.R.C. recorded in Liber 2,	L.C.R.C. recorded in
Set qr section post	Page 265, 8-6-73	Liber 3, Page 237, 12-21-77
Post	1/2" Rod Found	Replaced iron with cast iron monument inscribed "Ottawa County Section Corner"
Sugar 12 S69W 02	S.W. 18" Ash 37.71'	PK in Power Pole W 45.94'
Do 13 N61E 30	E. Sign Post 36.64'	Tack in Hub NE 57.84'
John Mullett, Deputy Surveyor	W.S.W. P.P. 24.76'	Tack in Hub E 41.25'
April 8, 1837		

(SEE REVERSE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-6 Found Cast Iron Monument inscribed "Ottawa County Section Corner", 4 1/2" below surface of asphalt pavement in Monument Box, and accepted as a careful and faithful perpetuation of the position of the original corner.

Found PK nail in North side of Power Pole	N88°W	45.86' (E)
Found PK nail in North side of Power Pole	N83°30'W	120.56' (E)
Cast Iron Monument in Monument Box	South	2676.20' (E)

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 10-21-96

*[Signature]*



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-6 Cast Iron Monument inscribed "Ottawa County Section Corner", 4 1/2" below surface of asphalt pavement in Monument Box.

Set Ottawa County Remon Tag & nail in East side of Power Pole	S07°30'W	351.99' (E)
South end, 12" Concrete Culvert (Chiselled "X")	S49°W	39.31' (E)
Set Ottawa County Remon Tag & nail in North side of Power Pole	N88°W	45.85' (E)
Set Ottawa County Remon Tag & nail in North side of Power Pole	N83°30'W	120.57' (E)
Set Ottawa County Remon Tag & nail in East side of Power Pole	N08°W	341.02' (E)
Centerline North & South asphalt road, 0.6' West		
Field line East & centerline ditch West, 9'± North		

Signed by

*[Signature: Donald W. Schiele]*

Date

October 21, 1996

Surveyor's Michigan License No.

23517

11.00

SURVEY &  
REMONUMENTATION

Section A., continued:

K-6

JED 05 2000

Unrecorded property survey by Carl P. Englert, Jr. dated 7-5-73:

Distance from E. 1/4 cor., Sec. 14 to SE cor., Sec. 14 2676.68'

SECTION

Certified Survey recorded in Liber 4, Page 411, 9-5-79:

CI Sec. Cor. marker

C/L MBT Junction Box E 32.3'

Nail in NW side P. Pole WSW 24.75'

PK in E. side P. Pole NNW 238.28'

Calculated distance, W. 1/4 cor., Sec. 13 to SW cor., Sec. 13 2676.10'

*[Faint, illegible handwritten or stamped text]*