

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:46

Reggie Robinson
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T 8N R 14W	K-8 (W 1/4, 24) Polkton Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Donald W. Schiele, in a field survey on December 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 K-8 1/4 corner common to Sections 23 & 24, Polkton Twp.

Original Government Corner Record:	L.C.R.C. recorded in Liber 2, Page 349, 10-31-73
Set qr section post between Sec. 23 & 24	Set 1" iron (in place of PK)
Post	SW cor. red house N70°E 55.40'
Sugar 12 S47E 17	NW cor. grey house S65°E 59.30'
Cherry 6 N 2W 31	7" Maple West 48.70'
John Mullett, Deputy Surveyor	P. pole East 19.35'
April 8, 1837	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 Found 2-3/4" dia. Cast Iron Monument (broken), 8" below surface, and accepted as a careful and faithful perpetuation of the position of the original corner.

SW frame corner to House # 410	N76°E	55.36'
Found PK nail in South side of Power Pole	S85°E	19.68'
Found nail in West side of Power Pole, 3.5' above ground	S85°E	19.34'
NW corner, foundation to House # 394	S64°E	59.27'
Found PK nail in East side of Telephone Pole	S10°30'E	88.48'
Found nail in North side of 12" Maple	S87°W	48.92'
Found nail in East side of Power Pole	N16°W	59.50'

P.A. 345 OTTAWA COUNTY

PEER APPROVED

12/12/94
Reggie Robinson

C. Description of monument for corner and accessories established to perpetuate the position of the corner:

K-8 Broken 2-3/4" dia. Cast Iron Monument, 8" below surface in Monument Box.

Centerline Fire Hydrant	N13°E	103.31'
SW frame corner to House # 410	N76°E	55.36'
NW corner, foundation to House # 394	S64°E	59.27'
Set Ottawa County Remon Tag & nail in SE side of 26" Maple	S30°W	68.64'
Set Ottawa County Remon Tag & nail in South side of 12" Maple	S87°W	48.92'
Set Ottawa County Remon Tag & nail in East side of Power Pole	N16°W	69.39'
On centerline asphalt road North & South		
On occupation line to East, ±		

Signed by Donald W. Schiele

Date Dec. 12, 1994

Surveyor's Michigan License No. 23517

