

**SURVEY & REMONUMENTATION**

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:47

*Daphne Kallman*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 8N R 14W	K-12 (W $\frac{1}{4}$ , 36) Polkton Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald W. Schiele, in a field survey on December 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 K-12  $\frac{1}{4}$  corner common to Sections 35 & 36, Polkton Twp.

Original Government Corner Record:	L.C.R.C. recorded in Liber 2, Page 815, 9-11-75	L.C.R.C. recorded in Liber 4, Page 306, 4-1-82
Set qr section post between Sec. 35 & 36 Post	Iron PK nail in first fence post South of corner	Set Cast Iron Monument 11" Ash NE 122.79'
Beech 14 N 5E 15	PK nail in corner fence post	Fence Post W 0.60'
Do 6 S18W 05	PK nail in first fence post North of corner	Fence Post N 8.13'
John Mullett, Deputy Surveyor April 8, 1837		Fence Post S 8.44'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 K-12 Found Cast Iron Monument inscribed "Section Corner", 3" below surface, and accepted as a careful and faithful perpetuation of the position of the original corner.

Found nail in West side of 17" Ash	N75°E	122.79'
Found nail & cap in East side of 6" X 6" Fence Post	South	8.47'
Found PK nail in East side of 6" X 6" corner Fence Post	West	0.29'
Found nail & cap in East side of 6" X 6" corner Fence Post	West	0.20'
Found nail & cap in East side of 6" X 6" Fence Post	North	8.09'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 Cast Iron Monument inscribed "Section Corner", 3" below surface.

Set Ottawa County Remon Tag & nail in West side of 18" Ash	N10°E	168.32'
Set Ottawa County Remon Tag & nail in South side of 14" Ash	N78°30'E	120.32'
Set Ottawa County Remon Tag & nail in East side of 6" X 6" Fence Post	South	8.44'
Set Ottawa County Remon Tag & nail in South side of 20" Ash	N89°W	57.72'

On fence lines North, South & West

P.A. 345 OTTAWA COUNTY

PEER APPROVED 12/12/94

*Madison P. Hedewald*  
 Date DEC. 12, 1994

Signed by Donald W. Schiele

Surveyor's Michigan License No. 23517