

FEB 24 2000

RECORDED

99 SEP -9 PM 12:15

OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Sam Sibley*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

SECTION  
For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T 8N R 14W	L-3 (N $\frac{1}{4}$ , 12)
	T ___ R ___	Polkton Twp.
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Donald W. Schiele, in a field survey on Aug. 24, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-3 1/4 corner common to Sections 1 & 12, Polkton Twp.  
 Original Government Corner Record: L.C.R.C. recorded in L.1, P.487, 7-6-72 by  
 Set qr section post on true line C.P. Englert, Jr.:  
 Post 1" Iron Pipe (SEE REVERSE)  
 Beech 9 S88 $\frac{1}{2}$ E 32 S.S.E. Tele. Pole  
 Do 7 N78 $\frac{1}{2}$ W 24 N.E. S.W. Cor. of House 105.1  
 John Mullett, Deputy Surveyor N. Power Pole 43.47  
 April 9, 1837

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-3 Found Cast Iron Monument (broken), 6" below surface of gravel road, and accepted as a careful and faithful perpetuation of the position of the original corner.  
 SW corner, foundation to House #5195 N33°30'E 105.28' (E)  
 Found nail in SW side of Telephone Pole S25°E 18.12' (E)  
 Found nail in SW side of Telephone Pole S25°E 18.14' (E)  
 Centerline 13" Boxelder S70°W 57.3' (E)  
 Found bent nail in NE side of Power Pole N03°30'W 43.73' (E)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-3 Broken Cast Iron Monument, 6" below surface of gravel road. N33°30'E 105.28' (E)  
 SW corner, foundation to House #5195 S25°E 18.14' (E)  
 Set Ottawa County Remon Tag & nail in NE side of Telephone Pole S70°W 57.30' (E)  
 Set Ottawa County Remon Tag & nail in North side of 13" Boxelder N45°W 76.47' (E)  
 Set Ottawa County Remon Tag & nail in SW side of 20" Poplar N03°30'W 43.47' (E)  
 Set Ottawa County Remon Tag & nail in West side of Power Pole  
 Centerline East & West gravel road, 9.5' North.  
 Fence line to North, 1.2' East.  
 Occupation line to South, 2'± East.

\$2.00 PHOTO  
 Receipt #56820  
 \$11.00 CORNER  
 Receipt #56820

Signed by Donald W. Schiele  
 Surveyor's Michigan License No. 23517

Date August 25, 1999

Part A., continued:

L.C.R.C. recorded in L.6, P.28, 1-3-90 by Thomas E. Joiner:

L-3

Set CIM

PP	N	43.52
SW Hse Cor	NE	105.30
6" Ash	SW	57.56
TP	SE	18.18

FEB 24 2000

SECTION