

**SURVEY &
REMONUMENTATION**

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 15 AM 11:46

D. W. Schiele
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa

(County)

Located in:

Corner Code #

1. Public Land Survey

T 8N R 14W

L-9 (S $\frac{1}{4}$, 24)

Polkton Twp.

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald W. Schiele, in a field survey on December 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-9 $\frac{1}{4}$ corner common to Sections 24 & 25, Polkton Twp.

Original Government Corner Record:

Set qr section post on true line between Sec. 24 & 25

Post

Beech 14 S56E 14

Sugar 12 N50W 20

John Mullett, Deputy Surveyor

April 8, 1837

L.C.R.C. recorded in Liber 5,

Page 253, 8-28-86

Set CIM

PP NW 159.40'

PP N 58.64'

Fence Post SE 89.27'

13" Tree SW 18.50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9 Found 2-3/4" dia. Cast Iron Monument inscribed "Section Corner", 5" below surface, and accepted as a careful and faithful perpetuation of the position of the original corner.

Found nail in East side of 13" stump

S22°W 18.50'

Found nail in East side of 13" stump

S22°W 18.48'

Found nail & Tag # RLS 18435 in SW side of Power Pole

N68°W 159.40'

Found nail & Tag # RLS 18435 in West side of Power Pole

N02°W 58.61'

Found PK nail in West side of Power Pole

N02°W 58.63'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 2-3/4" dia. Cast Iron Monument inscribed "Section Corner", 5" below surface in Monument Box.

Set Ottawa County Remon Tag & nail in North side of 16" Elm S83°30'E 146.73'

Set Ottawa County Remon Tag & nail in North side of 6" Walnut S74°W 101.04'

Set Ottawa County Remon Tag & nail in SW side of Power Pole N68°W 159.32'

Set Ottawa County Remon Tag & nail in West side of Power Pole N02°W 58.59'

On occupation line North, ±

Centerline asphalt road East & West, 4.5' North

P.A. 345 OTTAWA COUNTY

PEER APPROVED

12/12/94
Donald W. Schiele

Signed by

Donald W. Schiele

Date

DEC. 12, 1994

Surveyor's Michigan License No.

23517